



GOVERNMENT OF BIHAR

*NAME OF WORK :- Restoration work of Road L071-PMGSY
Vaishali to Gourihar Man Chhapra Vaishali Siman*

(FDR PART-A)

Restoration Length :- 0.060 KM

Block:- Sakra

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 094,300.00

**-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST I**

प्रतिवेदन

अथ का नाम:-

4725

आवकलित राशि - Rs. 94 300

प्रस्तुत प्राप्ति
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 08.03.2019 दिनांक 08.03.2019 के आदेश के अन्तर्गत उक्त पथ के क्षतिग्रस्त पथ में कोयला, बालू आदि का उपयोग कर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी वतनोत्तर स्वीकृति अपेक्षित है।

1.12.20
कनीय अभियंता

सहायक अभियंता

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुज0
पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- EE, RWD (w) WORKS DIV MUZA (FARRUK-EAST-1)
2 Name of Block/Road- SAKRA] L-71 - PM 6.54 Vaishali & gamhar
man (Kham Vaishali Sman.

A For Road

- 1 Damage Location/Chainage (0.2 m - 1.8 km) General Section
2 Damage Length 100 m 100 m
3 Nature of Damage 100 m 100 m
4 Details of Restoration Works-

- i Material being used in Restoration Works-
ii Equipments/Tools being used in Restoration Works-
iii Procedure Taken up in Restoration Works-
iv Restored Length

B. For Bridge

- 1 Damage Location/Chainage
2 Damage Length
3 Nature of Damage
4 Details of Restoration Works-
- i Material being used in Restoration Works-
ii Equipments/Tools being used in Restoration Works-
iii Procedure Taken up in Restoration Works-
iv Restored Length

Signature of JE/ AE/ EE

Signature

(Name of Inspector)

ME OF WORK:- Restoration work of Road L071-PMGSY Vaishali to Gourihar Man Chhapra Vaishali Siman

Total Length :- 1.912 KM

Restoration Length :- 0.060 KM

ABSTRACT OF COST

	Unit	Rates	Quantity	Amount
Providing and Laying of Brick Bats:				
Placing tractor at loading point loading with front end loader lumpsum, turning for return trip excluding time for haulage and return trip	Cum	1,768.60	44.90	79,410.00
Total Amount			Rs.	79,410.00
Add for GST @ 12%			Rs.	9,529.00
Add for Labour Cess @ 1%			Rs.	794.00
Add for Seigniorage Fee			Rs.	4,566.00
Gross Total Amount			Rs.	94,299.00
Say			Rs.	94,300.00

Ashutosh
12/12/20

J.E.

A.E.

RWD, Sub-Division, Sakra

8.12.20

Executive Engineer

RWD(W) Div.Muzaffarpur East 1

Total amount of Rs. 94300/- (Rupees Ninety four thousand
Three hundred only)

18/12/20
S.E.

R.W.D (W) CIRCLE
MUZAFFARPUR

Chhapra Vaishali Siman

Total Length :-

1.912 KM

Restoration Length :- 0.060 KM

Sl. No.	ITEM OF WORKS	Nos	Length	Breadth	Height	QTY	UNIT
1	<u>Providing and Laying of Brick Bats:</u>						
	Placing tractor at loading point loading with front end loader dumpong, turning for return trip exluding time for haulage and return trip						
		1 x 1	12 000	$\times \left(\frac{1.500 + 2.250}{2} \right)$	$\times \left(\frac{0.400 + 0.500}{2} \right)$	= 10.13	Cum
		1 x 1	15.000	$\times \left(\frac{2.000 + 2.500}{2} \right)$	$\times \left(\frac{0.450 + 0.350}{2} \right)$	= 13.50	Cum
		1 x 1	11.000	$\times \left(\frac{2.250 + 2.000}{2} \right)$	$\times \left(\frac{0.400 + 0.300}{2} \right)$	= 8.18	Cum
		2 x 1	5.000	$\times \left(\frac{1.750 + 2.250}{2} \right)$	$\times \left(\frac{0.550 + 0.400}{2} \right)$	= 9.50	Cum
		1 x 1	7.500	$\times \left(\frac{1.500 + 0.750}{2} \right)$	$\times \left(\frac{0.450 + 0.400}{2} \right)$	= 3.59	Cum
Total Quantity						= 44.90	Cum

Ashutosh Kumar
12/12/2020
I.E.

A.E.
RWD, Sub-Division, Sakra

Executive Engineer
RWD(W) Div.Muzaffarpur East 1