



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-	Bargawn to Shankarpur		
DISTRICT	Muzaffarpur		
DIVISION	Muzaffarpur East-1		
BLOCK	Bandra		
TOTAL LENGTH OF ROAD	:	10.750	KM
CONSTRUCTION COST	:	5.969	Lac

Submitted By :-
Executive Engineer
RWD Work Division Muzaffarpur East-1

प्रतिवेदन

कार्य का नाम:- T.O.2 बड़गाँव से शंकरपुर

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- बन्दरा

वित्तीय वर्ष - 2020-21

प्राक्कलित राशि - Rs. 5.969 लाख

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 5.969 लाख है, कार्य प्रमण्डल मुजफ्फरपुर स्वी-1, प्रखण्ड बन्दरा में यातायात बहाली हेतु आपातकालिन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में ईट लुकड़ा स्थानीय बाधु भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।

Kumar

11.11.2020
कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशासक बन्दरा

11.11.2020

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमण्डल बन्दरा

15.11.20

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमण्डल मुज0

पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- EXECUTIVE ENGINEER RWD (W) DIV. Muzaffarpur East-1
- 2 Name of Block/Road- Bardha / Bardgawan to Shewarapur


A For Road

- 1 Damage Location/Chainage At every places
- 2 Damage Length 137.15 mtr
- 3 Nature of Damage Road Breach (Complete traffic block)
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works- Brick Bat, local Sand
 - ii Equipments/Tools being used in Restoration Works- JCB, tractor, Road Roller, Manual
 - iii Procedure Taken up in Restoration Works- Immediate traffic restoration
 - iv Restored Length 137.15 mtr

B. For Bridge

- N/A
- 1 Damage Location/Chainage
 - 2 Damage Length
 - 3 Nature of Damage
 - 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length
- N/A

Signature of JE/ AE/ EE


Signature
(Name of Inspector)

GENERAL ABSTRACT

Name of Road Bargawn to Shankarpur

District Muzaffarpur

Block Bandra

Division Muzaffarpur East-1

Length of Road (in Km) 10.750 Km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Jhama metal	5.634
2	Sand Filling	0.336
3	H.P.	0.000
4	Bamboo Piles	0.000
	GRAND SUB TOTAL	5.969
TOTAL COST OF PROJECT IN LACS =		5.969

[Signature]
11.11.2020
JE

RWD

[Signature]
11.11.2020
AE

RWD

[Signature]
15.12.20

EE

RWD

Technically approved for Rs. 596900.00 (Rs. Five
lacs ninety six thousand nine hundred) only.

[Signature]
27/12/20 SE, RWD
Muzaffarpur

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Jhama metal Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalasi making and maintaining diversion light barrier - do - do- danger signal etc. all complete .				
			Appendix - I	Cum	277.07		
			Sand Filling	Total	277.07	2033.34	563377.51
2		11.20	Filling in foundation trenches as per drawing and technical specification Clause 305.3.9				
			Appendix - II	Cum	73.860		
			Total	Total	73.86	454.53	33571.59
Total Cost :-							596949.10

Sumit
11.11.2020
JS

18/11/2020
A.C

15.11.20
E.C