



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-		Bandra Mutlupur Mukhya Sadak to Pipar Pattiya Muslim Tola	
DISTRICT		Muzaffarpur	
DIVISION		Muzaffarpur East-1	
BLOCK		Bandra	
TOTAL LENGTH OF ROAD		:	1.500 KM
CONSTRUCTION COST		:	3.156 Lac

Submitted By :-
Executive Engineer
RWD Work Division Muzaffarpur East-1

प्रतिवेदन

कार्य का नाम:- बन्दरा - मुजफ्फरपुर मुख्य सड़क से पिपरपत्तीया मुस्लिम दोला

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- बन्दरा

वित्तीय वर्ष - 2020-21

प्राक्कलित राशि - Rs. 3.156 साठ

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 3.156 साठ है, कार्य प्रमण्डल मुजफ्फरपुर खी-1, प्रखण्ड बन्दरा में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521, दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में ईट टुकड़ा स्थानीय बालू भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।

Bunar
11.11.2020
कनीय अभियंता

ग्रामीण कार्य विभाग
कार्य प्रशासक बन्दरा

प्रिया
11.11.2020
सहायक अभियंता

ग्रामीण कार्य विभाग
कार्य प्रमण्डल बन्दरा

प्रिया
15.12.20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल मुज0
पूर्वी-1.

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- EXECUTIVE ENGINEER RWD (W) DIV. Muzaffarpur East-1
- 2 Name of Block/Road- Banda / Beside Muzaffarpur Muzaffarpur Sadak to Pipers Pathyga consignment.

A For Road

- 1 Damage Location/Chainage At every place
- 2 Damage Length 7.75 km
- 3 Nature of Damage Complete traffic block due to breach of Road,
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works- Police Bag, local Sand
 - ii Equipments/Tools being used in Restoration Works- JCB, Tractor, Road Roller, Manual
 - iii Procedure Taken up in Restoration Works- Immediate traffic Restoration
 - iv Restored Length 7.75 km

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length

Signature of JE/ AE/ EE

Signature
(Name of Inspector)

<u>GENERAL ABSTRACT</u>		
Name of Road	Bandra Mutlupur Mukhya Sadak to Pipar Pattiya Muslim Tola	
District	Muzaffarpur	
Block	Bandra	
Division	Muzaffarpur East-1	
Length of Road (in Km)	1.500 Km	

SI. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Jhama metal	3.071
2	Sand Filling	0.085
3	H.P.	0.000
4	Bamboo Piles	0.000
	GRAND SUB TOTAL	3.156
TOTAL COST OF PROJECT IN LACS =		3.156

JE
RWD

AE
RWD

EE
RWD

1/11/12
SE, QW
27/1/12 Woods Circle Hurstford

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Jhama metal Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalasi making and maintaining diversion light barrier - do - do- danger signal etc. all complete .				
			Appendix - I	Cum	151.05		
				Total	151.05	2033.34	307136.01
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical specification Clause 305.3.9				
			Appendix - II	Cum	18.630		
				Total	18.63	454.53	8467.89
Total Cost :-							315603.90

Barmer
11.11.2020
JC

11.11.2020
AE

15.12.20
CE