



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-		Ghosrana Middle School to Ghosrama Harijan Tola	
DISTRICT		Muzaffarpur	
DIVISION		Muzaffarpur East-1	
BLOCK		Bandra	
TOTAL LENGTH OF ROAD		:	1.950 KM
CONSTRUCTION COST		:	1.368 Lac

Submitted By :-
Executive Engineer
RWD Work Division Muzaffarpur East-1

प्रतिवेदन

कार्य का नाम: घोषरामा मिडल स्कूल से घोषरामा हरिजन टोला

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- बन्दरा

वित्तीय वर्ष - 2020-21

प्राक्कलित राशि - Rs. 1.368 लाख

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 1.368 लाख है, कार्य प्रमण्डल मुजफ्फरपुर खी-1, प्रखण्ड बन्दरा में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521, दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में ईट लुकड़ा स्थानीय ब्राह्मण भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।

Bhramar
11.11.2020
कनीय अभियंता

ग्रामीण कार्य विभाग
कार्य प्रशासक बन्दरा

शिशु
11.11.2020
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल बन्दरा

Shree
15.11.20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल मुजफ्फरपुर
पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- EXECUTIVE ENGINEER RWD (W) DIV. Muzaffarpur East-1
- 2 Name of Block/Road- Bamda / Ghosara Middle school to Ghosara Haripur tola.

A For Road

- 1 Damage Location/Chainage At many places
- 2 Damage Length 27.00 mtr
- 3 Nature of Damage Complete traffic block due to breach of road.
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works- Poricle Bat, Local sand
 - ii Equipments/Tools being used in Restoration Works- JB, Road Rotten Tractor, Manual
 - iii Procedure Taken up in Restoration Works- Immediate traffic restoration
 - iv Restored Length 27.00 mtr

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length

N/A

Signature of JE/ AE/ EE

Signature
(Name of Inspector)

GENERAL ABSTRACT

Name of Road Ghosrana Middle School to Ghosrama Harijan Tola

District Muzaffarpur

Block Bandra

Division Muzaffarpur East-1

Length of Road (in Km) 1.950 Km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Jhama metal	1.308
2	Sand Filling	0.061
3	H.P.	0.000
4	Bamboo Piles	0.000
	GRAND SUB TOTAL	1.368
TOTAL COST OF PROJECT IN LACS =		1.368

Bum
11.11.2022

JE

RWD

187A
11.11.2020

AE

RWD

15.12.20

EE

RWD

Technically approved for Rs. 136800 = 00 (Rs. one
lakh thirty six thousand eight hundred) only

187A
27.12.20
RWD Muzaffarpur
Muzaffarpur

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Jhama metal Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalasi making and maintaining diversion light barrier - do - do- danger signal etc. all complete .				
			Appendix - I	Cum	64.32		
				Total	64.32	2033.34	130784.43
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical specification Clause 305.3.9				
			Appendix - II	Cum	13.320		
				Total	13.32	454.53	6054.34
Total Cost :-							136838.77

Sum
11.11.2020
JL

(9) 11.11.2020
AL

15.12.20
EC