



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-		Mutlupur to Hatha	
DISTRICT		Muzaffarpur	
DIVISION		Muzaffarpur East-1	
BLOCK		Bandra	
TOTAL LENGTH OF ROAD		:	12.000 KM
CONSTRUCTION COST		:	6.576 Lac

Submitted By :-
Executive Engineer
RWD Work Division Muzaffarpur East-1

प्रतिवेदन

कार्य का नाम:- मुतल्लपुर से बच्चा

..... पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- बन्दरा

वित्तीय वर्ष - 2020-21

प्राक्कलित राशि - Rs. 6.576 लाख

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 6.576 लाख है, कार्य प्रमण्डल मुजफ्फरपुर स्वी-1, प्रखण्ड बन्दरा में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521, दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में ईट टुकड़ा स्थानीय बाधु भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।

Bhuma
11.11.2020
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रसारक बन्दरा

11.11.2020
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रसारक बन्दरा

15.11.20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल मुज0
पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- EXECUTIVE ENGINEER RWD (W) DIV. Muzaffarpur East-1
- 2 Name of Block/Road- Banohra / Mutulapur to Hathua

A For Road

- 1 Damage Location/Chainage At many places
- 2 Damage Length 135.50 Mtr
- 3 Nature of Damage Complete to the Block due to Breach of road.
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works- Bricle Bat, local sand
 - ii Equipments/Tools being used in Restoration Works- JCB, tractor, Road Roller, Manual
 - iii Procedure Taken up in Restoration Works- Immediate to the restoration.
 - iv Restored Length 135.50 mtr

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length

N/A

Signature of JE/ AE/ EE

Signature
(Name of Inspector)

GENERAL ABSTRACT

Name of Road Mutlupur to Hatha
District Muzaffarpur
Block Bandra
Division Muzaffarpur East-1
Length of Road (in Km) 12.000 Km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Jhama metal	6.399
2	Sand Filling	0.178
3	H.P.	0.000
4	Bamboo Piles	0.000
	GRAND SUB TOTAL	6.576
TOTAL COST OF PROJECT IN LACS =		6.576

Burner
11.11.2020
JE
RWD

127
11.11.2020
AE
RWD

15.12.20
EE
RWD

Technically approved form. 657600=00 (i.e. Six lacs
fifty seven thousand six hundred) only.

15.12.20
SE, RWD
Wones Creek, Muzaffarpur

SI. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Jhama metal Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalasi making and maintaining diversion light barrier - do - do- danger signal etc. all complete .				
			Appendix - I	Cum	314.68		
				Total	314.68	2033.34	639851.43
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical specification Clause 305.3.9				
			Appendix - II	Cum	39.130		
				Total	39.13	454.53	17785.76
Total Cost :-							657637.19

Bihar
11.11.2020

11.11.2020
A.E

1572.20