



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-		Bandra to Mutlupur	
DISTRICT		Muzaffarpur	
DIVISION		Muzaffarpur East-1	
BLOCK		Bandra	
TOTAL LENGTH OF ROAD		:	3.950 KM
CONSTRUCTION COST		:	2.753 Lac

Submitted By :-
Executive Engineer
RWD Work Division Muzaffarpur East-1

प्रतिवेदन

कार्य का नाम— बन्दरा से मुजफ्फरपुर

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड— बन्दरा

वित्तीय वर्ष — 2020-21

प्राक्कलित राशि — Rs. 2.753 लाख

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 2.753 लाख है, कार्य प्रमण्डल मुजफ्फरपुर खी-1, प्रखण्ड बन्दरा में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में ईट टुकड़ा स्थानीय बाधु भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।

Sumar
11.11.2020

कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशासक बन्दरा

श्रीम
11.11.2020

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमण्डल बन्दरा

Sumar
15.11.20

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमण्डल मुजफ्फरपुर

पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- EXECUTIVE ENGINEER RWD (W) DIV. Muzaffarpur East-1
- 2 Name of Block/Road- Banaha / Banaha to Muzaffarpur

A For Road

- 1 Damage Location/Chainage At many places.
- 2 Damage Length 63 mts
- 3 Nature of Damage Complete to the Block due to Breaching of road,
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works- Brick Bat, local sand
 - ii Equipments/Tools being used in Restoration Works- Road Roller, Tractor, JCB, Manual
 - iii Procedure Taken up in Restoration Works- Immediate to the restoration
 - iv Restored Length 63 mts

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length

N/A

Signature of JE/ AE/ EE

Signature
(Name of Inspector)

GENERAL ABSTRACT

Name of Road Bandra to Mutlupur

District Muzaffarpur

Block Bandra

Division Muzaffarpur East-1

Length of Road (in Km) 3.950 Km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Jhama metal	2.678
2	Sand Filling	0.075
3	H.P.	0.000
4	Bamboo Piles	0.000
	GRAND SUB TOTAL	2.753
TOTAL COST OF PROJECT IN LACS =		2.753

[Signature]
11-11-2020
JE
RWD

[Signature]
11-11-2020
AE
RWD

[Signature]
15-11-20
EE
RWD

Technically approved for Rs. 275800 = 00 (Rs. Two
lacs seventy five thousand three hundred) only.

[Signature]
27/11/2020
27/11/2020
Waste Circle, Muzaffarpur

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Jhama metal Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalasi making and maintaining diversion light barrier - do - do- danger signal etc. all complete .				
			Appendix - I	Cum	131.7		
				Total	131.70	2033.34	267790.88
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical specification Clause 305.3.9				
			Appendix - II	Cum	16.500		
				Total	16.50	454.53	7499.75
Total Cost :-							275290.63

Bhumer
11.11.2020
JL

911
11.11.2020
AL

911
11.11.20
EL