



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :- NH-77 Dhorilala to Chakdora

DISTRICT Muzaffarpur

DIVISION Muzaffarpur East-1

BLOCK Kudhani

TOTAL LENGTH OF ROAD	:	1.950	KM
CONSTRUCTION COST	:	1.042	Lac

Submitted By :-
Executive Engineer
RWD Work Division Muzaffarpur East-1

प्रतिवेदन

कार्य का नाम:- NH-37 दोही चाला से चकड़ीरा

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- कुदनी

वित्तीय वर्ष - 2020-21

प्राक्कलित राशि - Rs. 1.042 लाख

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 1.042 लाख है, कार्य प्रमण्डल मुजफ्फरपुर पूर्वी-1 प्रखण्ड कुदनी में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में ड्रैट लुकाड़ा, स्थानीय बाध भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।

Bhambh
11.11.2020

कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा कुदनी-1

K. Anubh
11/11/2020

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमण्डल

कुदनी

15.12.20

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल मुज0

पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- EXECUTIVE ENGINEER RWD (W) DIV. Muzaffarpur East-1
2 Name of Block/Road- Kuchhori / NH-77 Short Lalq. to Chakdora

A For Road

- 1 Damage Location/Chainage At many places
2 Damage Length 8.25 km
3 Nature of Damage Complete Traffic Block due to Breach of Road
4 Details of Restoration Works-
i Material being used in Restoration Works- stone, Local Sand, Brickbat
ii Equipments/Tools being used in Restoration Works- Stone Roller, Tractor
iii Procedure Taken up in Restoration Works- Immediate Traffic Restoration
iv Restored Length 8.25 km

B. For Bridge

- 1 Damage Location/Chainage
2 Damage Length
3 Nature of Damage
4 Details of Restoration Works-
i Material being used in Restoration Works-
ii Equipments/Tools being used in Restoration Works-
iii Procedure Taken up in Restoration Works-
iv Restored Length

N/A

Signature of JE/ AE/ EE


Signature
(Name of Inspector)

GENERAL ABSTRACT

Name of Road NH-77 Dhorl Lala to Chakdora

District Muzaffarpur

Block Kudhani

Division Muzaffarpur East-1

Length of Road (in Km)

1.950 Km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Jhama metal	0.865
2	Sand Filling	0.020
3	H.P.	0.157
4	Bamboo Piles	0.000
	GRAND SUB TOTAL	1.042
TOTAL COST OF PROJECT IN LACS =		1.042

Bumr
11-11-2020
JE
RWD

K. Anish
11/11/20
AE
RWD

Spice
15-12-20
EE
RWD

Technically approved for Rs. 104200=00 (Rs. one
lax four thousand two hundred) only.

Shm
28-12-20
24/12/20 SE, RWD
Wore Chete, Muzaffarpur

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Jhama metal Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalasi making and maintaining diversion light barrier - do - do- danger signal etc. all complete .				
			Appendix - I	Cum	42.54		
				Total	42.54	2033.34	86498.28
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical specification Clause 305.3.9				
			Appendix - II	Cum	4.350		
				Total	4.35	454.53	1977.21
Total Cost :-							88475.49

[Signature]
15.12.20