

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

CIRCLE – R.W.D. works Circle, Chapra

DIVISION – R.W.D. works Division , Chapra-2

Name of Work - Restoration/Mottrable of Road from Agothar Nanda
sri Ram Manjhi ke Ghar se Dakshin Agothar
Sundar Tak

Block - Isuapur

Estimated cost - Rs 49906.00

Year : 2020-21

Inspection Report for flood damage work

Date:

1. Name of PIUs-

2. Name of Block/Road- Isuapur / Restoration / Motorable of Road from Agolhar
Nanda Sri Ram Manjhi ke ghari se Pakhal Agolhar Sundar tal

A. For Road

1. Damage Location/Chainage : - 30 M, 700 M, 850 M, 1050 M

2. Damage Length : 2.70 M, 13.00 M, 17.30 M, 8.70 M

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works: Tractor, Road Roller

iii Procedure taken up in Restoration works :

iv Restored Length : 72 M

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

20/11/20
20/11/20

Signature of JE/AF/EE

Vinod Kumar
Signature

VINOD KUMAR
(Name of Inspector)
Executive Engineer
R.W.D. (W) Division Chabutra

प्रतिवेदन

कार्य का नाम :- Restoration/Motable of Road from Agolhar ~~to~~ Nanda Sri
शीर्ष :- FDR Ram Manjhi ke ghar se Dakshin Agolhar Sunder tale.
प्राक्कलित राशि:- 49906 = ₹
प्रखण्ड का नाम:- Isuapur जिला-सारण।

प्रस्तुत प्राक्कलन शीर्ष PMGSY/MMGSY/GTSNY/NABARD/MR-3054 अर्तगत निर्मित/निर्माणाधीन पथ के गत महीने में इस जिला में आये बाढ़/अतिवृष्टि के कारण क्षतिग्रस्त हुए पथों को चलने लायक (Motarable) बनाने हेतु विभागीय दिशा-निर्देशानुसार कार्यपालक अभियंता, ग्रा0का0वि0, कार्य प्रमंडल Chapra-2 के दिशा-निर्देशन में कुल रु0 49906 = ₹ के लिए तैयार किया गया है।

आवश्यकतानुसार तत्काल प्रभाव से पथों को चलने लायक बनाने हेतु प्राक्कलन में Bricks Batts, Sand Bag, Hume-Pipe इत्यादी का प्रावधान आवश्यक लम्बाई, चौड़ाई एवं मोटाई में प्राक्कलन के अनुसार प्रावधान किया गया है।

योजना एवं कार्य की महत्ता के साथ-साथ जनहित के लिए अतिउपयोगी प्राक्कलन को कार्यहित में स्वीकृति हेतु प्रस्तुत किया जा रहा है।

[Signature]
23/12/20
जंर

[Signature]
23.12.2020
AC

[Signature]
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, Chapra-2।

ABSTRACT OF COST

Name of Work - Restoration/Mottrable of Road from Agothar Nanda sri Ram Manjhi ke Ghar se Dakshin Agothar Sundar Tak

Block - Isuapur

S.L No.	Particulars	Amount (In Rs.)
A	Cost of Restoration work	Rs 44164.00
B	Add 12 % GST on (A)	Rs 5300.00
C	Add 1 % L. Cess on (A)	Rs 442.00
	Total Cost	Rs 49906.00

[Signature]
23/12/20
J.E
RWD
Chapra-2

[Signature]
23/12/20
A.E
R.W.D
Chapra-2

[Signature]
23/12
E.E
R.W.D
Chapra-2

T/A for Rs 49906.00 (forty nine thousand
nine hundred and six only.)
[Signature]
28-12-20

Detailed Estimate

of work

Restoration/Mottrable of Road from Agothar Nanda sri Ram Manjhi ke Ghar se
Dakshin Agothar Sundar Tak

I No	Item	No	Length	Width	Avg.H/D	Qty	Unit	Rate	Amount
1	Construction of granular sub-base by providing well graded gading-II material, all complete job-----E/I	1	2.70	3.75	0.10	1.01			
		1	13.00	0.525	0.10	0.68			
		1	13.00	1.10	0.10	1.43			
		1	17.30	0.525	0.10	0.91			
		1	17.30	1.30	0.10	2.25			
		1	8.70	0.90	0.20	1.57			
		Total					7.85	cum	3346.45
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, , all complete job-----E/I	1	2.70	3.75	0.075	0.76			
		1	13.00	1.10	0.075	1.07			
		1	17.30	1.30	0.075	1.69			
		1	8.70	0.90	0.075	0.59			
Total					4.11	cum	4353.73	17894.00	
TOTAL								44164.00	

[Signature]
23/12/20
J.E
RWD
Chapra-2

[Signature]
23/12/20
A.E
R.W.D
Chapra-2

[Signature]
23/12
E.E
R.W.D
Chapra-2