

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

CIRCLE – R.W.D. works Circle, Chapra

DIVISION – R.W.D. works Division, Chapra-2

Name of Work - Restoration/Mottrable of Road from L043 Chakhan
to T-04 Kerwa

Block - Isuapur

Estimated cost - Rs 235791.00

Year : 2020-21

Inspection Report for flood damage work

Date:

1. Name of PIU:-

2. Name of Block/Road- 244pur | Restoration | Notable of Road from Lvs
Chakhan To To4 Kerna

A. For Road -

1. Damage Location/Chainage : -200M, 250M, 1800M, 2600M, 2100M, 2300M

2. Damage Length : 25.00M, 23.00M, 1.20M, 0.90M, 3.50M, 11.00M, 1.10M

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

: Brick bats / local sand

ii Equipment/Tools being used in Restoration works:

Tractor, static road roller.

iii Procedure taken up in Restoration works

iv Restored Length

: 71.70 M.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

:

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

:

iv Restored Length

:

Signature of JE/AF/EE
23/12/20
23/12/20
23/12

Signature
VINOD KUMAR
(Name of Inspector)
Executive Engineer
R.W.D. (W) Division Chakhan

प्रतिवेदन

कार्य का नाम :- Restoration/Motable of Road from Loh Chalchar to Tola Kerna

शीर्ष :- FDR

प्राक्कलित राशि:- 2,35,791/-

प्रखण्ड का नाम:- Isuapur

जिला-सारण।

प्रस्तुत प्राक्कलन शीर्ष PMGSY/MMGSY/GTSNY/NABARD/MR-3054 अर्तगत निर्मित/निर्माणाधीन पथ के गत महीने में इस जिला में आये बाढ़/अतिवृष्टि के कारण क्षतिग्रस्त हुए पथों को चलने लायक (Motarable) बनाने हेतु विभागीय दिशा-निर्देशानुसार कार्यपालक अभियंता, ग्रा0का0वि0, कार्य प्रमंडल Chapra-2 के दिशा-निर्देशन में कुल रु0 2,35,791/- के लिए तैयार किया गया है।

आवश्यकतानुसार तत्काल प्रभाव से पथों को चलने लायक बनाने हेतु प्राक्कलन में Bricks Bais, Sand Bag, Hume-Pipe इत्यादी का प्रावधान आवश्यक लम्बाई, चौड़ाई एवं मोटाई में प्राक्कलन के अनुसार प्रावधान किया गया है।

योजना एवं कार्य की महत्ता के साथ-साथ जनहित के लिए अतिउपयोगी प्राक्कलन को कार्यहित में स्वीकृति हेतु प्रस्तुत किया जा रहा है।

23/12/20
ज६

23.12.20
AE

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, Chapra-2।

ABSTRACT OF COST

Name of Work - Restoration/Mottrable of Road from L043 Chakhan to T-04 Kerwa

Block - Isuapur

S.L No.	Particulars	Amount (In Rs.)
A	Cost of Restoration work	Rs 208664.00
B	Add 12 % GST on (A)	Rs 25040.00
C	Add 1 % L. Cess on (A)	Rs 2087.00
	Total Cost	Rs 235791.00

[Signature]
23/12/20

J.E
RWD
Chapra-2

[Signature]
23/12/2020

A.E
R.W.D
Chapra-2

[Signature]
23/12

E.E
R.W.D
Chapra-2

T/A for Rs 235791.- (Two lakh thirty five thousand seven hundred and ninety one only)
28.12.20

Detailed Estimate

of work :-

Restoration/Motrable of Road from L043 Chakhan to T-04 Kerwa

No	Item	No	Length	Width	Avg.H/D	Qty	Unit	Rate	Amount
1	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	25.00	1.60	1.10 (N)	44.00			
		1	23.00	1.20	1.05 (N)	28.98			
		1	1.20	0.90	0.30	0.32			
		1	0.90	0.75	0.30	0.20			
		1	3.50	0.90	0.90 (N)	2.84			
		1	11.00	1.30	1.50 (N)	21.45			
		1	1.10	3.75	0.45	1.86			
		1	1.50	3.75	0.30	1.69			
		1	1.50	3.75	0.30	1.69			
		1	1.50	3.75	0.30	1.69			
		1	1.50	3.75	0.30	1.69			
Total						106.41	cum	1909.87	203229.00
2	Filling and spreading local sand over brick bats as per drawing and technical specification Clause 305.3.9	1	25.00	1.60	0.10	4.00			
		1	23.00	1.20	0.10	2.76			
		1	1.20	0.90	0.10	0.11			
		1	0.90	0.75	0.10	0.07			
		1	3.50	0.90	0.10	0.32			
		1	11.00	1.30	0.10	1.43			
		1	1.10	3.75	0.10	0.41			
		1	1.50	3.75	0.10	0.56			
		1	1.50	3.75	0.10	0.56			
		1	1.50	3.75	0.10	0.56			
		1	1.50	3.75	0.10	0.56			
		1	0.00	0.00	0.10	0.00			
Total						11.34	cum	479.27	5435.00
TOTAL								208664.00	


 J.E.
 R.W.D
 Chapra-2


 A.E.
 R.W.D
 Chapra-2


 E.E.
 R.W.D
 Chapra-2