

Inspection Report For Flood Damage Work

Date :

1 Name of PIUs: Gopalgarh- 2

2 Name of Block/Road: Baikunthpur / PMGSY Kali Sthan To Baikunthpur
Haripur Pals

A For Road

1 Damage Location / Chainage: 1509 to 320 m, 700 to 910 m

2 Damage Length: 324 m

3 Nature of Damage: Heavy Rain / Flood

4 Details of Restoration Works:

i. Material being used in Restoration Works: Brick Bats

ii Equipments / Tools being used in Restoration Works: D/B, Trencher, Trolly, Reel, Shovel
Roller

iii Procedure taken up in Restoration Works: Yes

iv Restored Length: 324 m

B For Bridge

N/A

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

4 Details of Restoration Works:

i. Material being used in Restoration Works :

ii Equipments / Tools being used in Restoration Works :

iii Procedure taken up in Restoration Works:

iv Restored Length :

Plut
25/9/2022
JE25.09.2022
AE25/9/20
EESignature
Executive Engineer
(Name of Inspector)
R.W.D. W.D.
Hathua

Report

Name of Work :- Motorable work of PMGSY Kali Sthan To Baikunthpur Harijan Tola

Estimated Cost :- 3997500.00 3724600.00


Total length of Road :- 1.875 km

Description :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road. Hence there has been a provision of laying 1 Nos of R.C.C. NP3 1000 MM Dia hume pipe.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.


19/9/2020
J.E.


19.09.2020
A.E.


19/9/20
E.E.

Detailed Estimate For Motorable Work in Road from PMGSY Kali Sthan To Baikunthpur Harijan Tola damaged due to Heavy rain/flood for year 2020-2021

Sr.	Items	No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amount
1	Providing brick bats billed in ditches including all cost of labour & material with all complete job.								
	CH - 150 M to 320 M	2	30.00	6.00	2.65	922.20	M3		
		1	24.00	6.00	2.90	417.60	M3		
		1	26.00	1.40	0.60	21.84	M3		
		1	30.00	1.10	0.80	26.40	M3		
		1	28.00	1.00	0.47	13.02	M3		
		1	26.00	1.62	0.30	12.64	M3		
	CH - 700 M to 810 M	1	23.00	1.65	1.20	45.54	M3		
		1	4.00	1.30	0.85	4.42	M3		
		2	14.00	1.00	1.20	33.60	M3		
		2	6.00	1.20	2.00	28.80	M3		
		1	8.00	2.00	0.50	8.00	M3		
		1	3.00	1.30	0.20	0.78	M3		
		1	11.00	1.05	0.30	3.47	M3		
		1	19.00	1.45	0.50	13.78	M3		
		1	22.00	1.60	1.10	38.72	M3		
	Less for H.P.	0.79	1.23	1.23	0.60	0.72	M3	2412.11	3643540.20
						1621.88		2427.65	3937354.28
2	Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	2	2.50			1510.52	M	2744.50	13723
						5.00	M	4159.56	20797.80
									3687821.50
								3657263	3958152.08
	Add 1 % Contingency							36573	39581.52
						3693836.20	Total		3997733.60
					36.938	36.938	Say		3997500.00

Say Rs 39,97,500/-
37,24,600.00

[Signature]
19/9/2020

J.E.

[Signature]
19.09.2020


A.E.

[Signature]
19/9/20

E.E.

Technically Approved for Rs 39.975 Lacs (Rupees Thirty Nine Lacs Ninety Seven Thousand & Five Hundred) only

Technically Approved for Rs. 36,938 (Rupees) Thirty Six
Ninety Three Thousand & Eight Hundred only



अधीक्षक अभियंता
गांधी नगर विभाग, नया दिल्ली

P/24/11/2010
24/11/2010

Name of Road :- PMGSY Kali Sthan to Baikunthpur Harizan Tola



19/9/2020

19.09.2020

Name of Road :- PMGSY Kali Sthan to Baikunthpur Harizan Tola



Chil
19/9/2020
N

Chil
19/9/2020
P.V.