

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Jhama metal <u>Back Boat (100m)</u> Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalasi making and maintaining diversion light barrier - do - do - danger signal etc. all complete .				
			Appendix - I	Cum	166.19		
			Total	Total	166.19	1901.13	315948.79
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical specification Clause 305.3.9			<u>2033.34</u>	<u>337921.00</u>
			Appendix - II				
				Cum	20.450		<u>8226.00</u>
			Total	Total	20.45	402.24	8225.81
			Total Cost :-				324174.60

Rs. 316147.00

✓
27.11.20

Assty
27.11.20
A.E.

GENERAL ABSTRACT

Name of Road: Awawakarpur Kowahi P.A. Soni la Rai Ke Ghar to Yadav Tola Mushar Tola Patepur High School
 District: Tak
 Block: Vaishali
 Division: Patepur
 Mahua

Length of Road (in Km)

2.100 Km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Jhama metal Bricks Box (1000)	
2	Sand Filling	3.379 3.169
3	Sand bag	0.082
4	Bamboo Piles	0.000
	SUB TOTAL OF INTIAL RECTIFICATION	0.000
	1 % LABOUR CESS	3.461 3.243
	12 % GST	0.035 0.032
	GRAND SUB TOTAL OF INTIAL RECTIFICATION INDLUCDING SURFACE RENEWAL	0.415 0.389
	AVERAGE COST PER KM (IN LACS) =	3.663
	TOTAL COST OF PROJECT IN LACS =	2.157 1.744
		3.663

Rs 3.911

Ad 10% CP - 0.346

T = Rs. 4.257

27/11/20
 JE
 RWD

27/11/20
 AE
 RWD

27.11.20
 कार्यपालक अभियंता
 कार्य विभाग
 कार्य प्रमंडल, महुआ

T/A for Rs 4.257 Lacs (Four thousand two hundred and fifty seven thousand eight hundred and eighty nine only)

Superintending Engineer
 B.W.D. WORKS CIRCLE
 MUZAFFARPUR

27/11/20
 J.E.

27/11/20

T/A for Rs 3.911 (Three lakh ninety one thousand one hundred and eleven only)

27/11/20
 Superintending Engineer
 B.W.D. WORKS CIRCLE
 MUZAFFARPUR

Name of Road :-

Awawakarpur Kowahi P.A. Soni la Rai Ke Ghar to Yadav Tola Mushar Tola Patepur High School Tak

Block :-

Patepur


Appendix - II

Measurement for Surfacing the breach Sand Filling


S. No	Chainage	Nos	Length (M)	Width (M)	Av. Width (M)	Thickness (M)	Av. Thickness (M)	Quantity (Cum)
1		1	11	(6+9.5)/2	7.75	0.2	0.2	17.05
2		1	10		1.2	0.2	0.2	2.4
3		1	5		1	0.2	0.2	1
Total								20.45



Junior Engineer,
Rural Works Department,
Work Section,
Mahua



Assistant Engineer,
Rural Works Department,
Work Sub Division,
Mahua



Executive Engineer,
Rural Works Department,
Work Division,
Mahua

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Jhama metal <i>Back Bat (200m)</i> Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalasi making and maintaining diversion light barrier - do - do- danger signal etc. all complete .	Cum	166.19		
			Appendix - I	Total	166.19	1901.13	315948.79
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical specification Clause 305.3.9			2033.34	387921.00
			Appendix - II	Cum	20.450		8226.00
			Total	Total	20.45	402.24	8226.81
			Total Cost :-				324174.60

Rs. 316147.00

✓
27.11.20


Approved
27.11.20
A.D.


Name of Road :- Awawakarpur Kowahi P.A. Soni la Rai Ke Ghar to Yadav Tola Mushar Tola Patepur High School Tak


Block :- Patepur

Appendix - I

Measurement for Surfacing the breach Brick Bats								
S. No	Chainage	Nos	Length (M)	Width (M)	Av. Width (M)	Thickness (M)	Av. Thickness (M)	Quantity (Cum)
1		1	11	$(6+9.5)/2$	7.75			
2		1	10		1.2	$(1.2+0.8)/2$	1.75	149.19
3		1	5		1	$(1.4+0.6)/2$	1.00	12
Total								5
								166.19


Junior Engineer,
Rural Works Department,
Work Section,
Mahua
Patepur


Assistant Engineer,
Rural Works Department,
Work Sub Division,
Mahua


Executive Engineer,
Rural Works Department,
Work Division,
Mahua

Inspection Report for Flood Damage Work

Date:

1. Name of PIUs - EE, RWD, MAHVA

2. Name of Block/Road - Partapur, / Awawakarapur Roahi P.A. Soni
Lal Rai ke ghar to yadav Tola musthar
tole Partapur high school tak

A. For Road

1. Damage Location/Chainage : 1020 to 1031

2. Damage Length : 11.0 mtr

3. Nature of Damage : from flood.

4. Details of Restoration Works :

- Material being used in Restoration works : Bricks balt & Thama boulders.
- Equipments/Tools being used in Restoration works:
- Procedure taken up in Restoration works :
- Restored Length :

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration Works :

- Material being used in Restoration works :
- Equipments/Tools being used in Restoration works:
- Procedure taken up in Restoration works :
- Restored Length :

Signature of JE/AE/EE Aswinder
27/11/20
AE

Signature 14/11/20

(Name of Inspector)

27-11-20

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, महाराष्ट्र

अधीक्षण अभियंता का कार्यालय

ग्रामीण कार्य विभाग, कार्य अंचल, मुजफ्फरपुर

पत्रांक

प्रेषक;

(166.4.31)

28/12/20

मुज0/दिनांक 26.12.2020

अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, मुजफ्फरपुर।

सेवा में,

मुख्य अभियंता-04/
ग्रामीण कार्य विभाग,
बिहार, पटना।

विषय :- शीर्ष मुख्यमंत्री ग्राम संपर्क योजना पुनरीक्षित प्राक्कलन के तकनीकी स्वीकृति के संबंध में।

प्रसंग :- कार्यपालक अभियंता महोआ का पत्रांक 2713 महोआ, दिनांक 01.12.2020

महाशय,

उपर्युक्त विषयक मुख्यमंत्री ग्राम संपर्क योजना अवयकरपुर कोआही पंचायत अंतर्गत सोनी लाल राय के घर से यादव टोला, मुशहर टोला होते हुए पातेपुर हाईस्कूल तक पथ में आये बाढ़ में क्षतिग्रस्त हुए भाग को motorable किया गया एवं क्षतिग्रस्त सड़क का पुनरीक्षित प्राक्कलन का प्रतिहस्ताक्षरित कर तकनीकी स्वीकृति हेतु समर्पित की जा रही है।

अनु0-वथोक्त।

विश्वासभाजन

अधीक्षण अभियंता,

ग्रामीण कार्य विभाग,

कार्य अंचल, मुजफ्फरपुर