

GOVERNMENT OF BIHAR

UNDER FLOOD DAMAGE REPAIR 2020

Estimate for Restoration of Traffic

DISTRICT : WEST CHAMPARAN BLOCK : MAJHAULIA

YEAR(2020-2021)

NAME OF ROAD : BAGHAMBARPUR TO SEMRAGHAT [2.1 km]

Total Length	:	0.240	KMS	
Cost of Pavement (Rs.)	:	1015253		
Total Cost Of Road (Rs.)	:	1015253		

SUBMITTED BY

Executive Engineer RWD

Works Division, Bettiah

बिहार सरकार
ग्रामीण कार्य विभाग

पत्रांक - मु0अ0-4 (मु0) विविध (कार्य)-23-40/16 - 2254

पटना, दिनांक 30/6/2020

प्रेषक,

पंकज कुमार पाल,
सचिव

सेवा में,

सभी कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
बिहार, पटना।

विषय-

संभावित अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त पथों के आपातकालीन मरम्मत के संबंध में।


महाशय,

उपर्युक्त विषय के संबंध में कहना है कि राज्य में मानसून अति सक्रिय है जिसके कारण बाढ़ प्रवण जिलों में पथों के क्षतिग्रस्त होने की संभावना है। अतः निदेश दिया जाता है कि वर्तमान मानसून के दौरान अतिवृष्टि/बाढ़ से क्षतिग्रस्त पथों को मोटरेबुल बनाने का कार्य तत्परता से प्राथमिकता में किया जाय जिससे कि पथों में यातायात कम से कम समय तक बाधित रहे। इस क्रम में यह भी निदेश है कि जिला प्रशासन के साथ वर्षा-अवधि के दौरान लगातार समनव्य रखी जाय एवं उनसे प्राप्त पथों की मरम्मत का कार्य प्राथमिकता में कराया जाय।

ऐसे पथ जिनकी अनुरक्षण नीति के अन्तर्गत मरम्मत कार्य की निविदा प्रक्रिया में है उनको भी मोटरेबुल बनाए रखना विभाग का दायित्व है। इन्हें मोटरेबुल बनाए रखने में यदि प्राक्कलन में प्रावधानित मदों का उपयोग किया जाना आवश्यक हो तो वैसे स्थिति में एकरारनामा करने के समय इन मदों की उतनी मात्रा परिमाण विपत्र में से घटा दिया जाए।

क्षेत्रीय पदाधिकारी वर्षा-अवधि के दौरान बिना जिलाधिकारी अथवा अधोहस्ताक्षरी की अनुमति के मुख्यालय नहीं छोड़ेंगे।


विश्वासभाजन


(पंकज कुमार पाल)
सचिव

ज्ञापक:- मु0अ0-4 (मु0) विविध (कार्य)23-40/16 - 2254

पटना, दिनांक 30/06/20

प्रतिलिपि:- सभी प्रमंडल आयुक्त/जिलाधिकारी/सभी मुख्य अभियंता/सभी अधीक्षण अभियंता
ग्रामीण कार्य विभाग, बिहार, पटना को सूचनार्थ एवं आवश्यक कारवाई हेतु प्रेषित।


सचिव
30/06/20

TECHNICAL REPORT

Name of Road :- BAHAMBER PUR TO SEMRAHAT [2.1 KM]
Name of Block :- Majhulia.
Name of Division :- Works Division, Bettiah
Name of District :- West Champaran.
Estimated Cost :- Rs- 1015253=00.
Restoration Length :- 240M

This Estimate is prepared for Restoration of BAHAMBER PUR TO SEMRAHAT
[2.1 KM]

.....road under FDR as per the instruction of Secretary, Rural Works Department, Patna vide,

ज्ञापक:- मु0अ0 -4 (मु0) विविध (कार्य) 23 -40 /16-2254 पटना, दिनांक 30.06.2020. Road remains effected from flooded about 01 to 02 weeks and heavy amount of water passed through it.


Honorable Chief Minister/Secretary, Rural Works Department, Bihar, Patna/D.M., West Champaran, Bettiah/Concerned MP/MLA has instructed to maintain the traffic and movement of public etc. at the earliest so that public of this area may get connected and for the same Departmental instruction has also been issued to fill the gap made by flooded immediately.

The area surrounding is submerged in water and hence provision ofbricks bats :.....
.....has been made to maintain the road damage due to flood/heavy rainfall as per availability of material from available place by tractor. Presently there is no Contractor is employed for Construction and Maintenance of this road hence the work has been carried out Departmentally and due to this, provision of Contractor profit is not mentioned in the estimate.


In view of above, it is requested to approve the estimate amounting to Rs.

please.

Submitted for Technical Approval please.


Assistant Engineer,
Majhulia


Assistant Engineer,
Majhulia


Executive Engineer
R.W.D.(W) Division, Bettiah

COST ESTIMATE FOR traffic Restoration

Name of Road: BAGHAMBARPUR TO SEMRAGHAT
District: WEST CHAMPARAN

Block: MAJHAULIA
Cutting length

Length: 240.000 m
240 M

S. No.	SOR Item No.	Description	No	Length (M)	Width (M)	H/D (M)	Qty.	Unit	Rates (in Rs.)	Amount
5	RCD	Laying brick bats on prepared soil surface as per Specification & direction of Engineer Incharge								
		As per measurement					500.87	cum	1703.77	853375.05
		Total Road work								853375.05
		Say Rs.								853375.05
		Add GST @12%								102405.01
		Add Labour Cess @1%								8533.75
		Add Seignrage Fee@10% of basic material rate								50938.83
		Total Cost of work								1015252.64
		Say Total Rs.								1015253

For
12/10/20
J.E

12/10/20
AC

1
12/10/20
ET

Detailed Measurement Brick Bat				
No	L(m)	W(m)	D(m)	Qty(cum)
1	110	$(1.50+1.0)/2$	$(2.0+1.1)/2$	213.125
1	100	$(1.75+1.20)/2$	$(2.10+1.50)/2$	265.500
5	2.75	2.1	0.30	8.663
3	2.8	2.2	0.45	8.316
1	2.6	2	0.35	1.820
2	2.5	2.3	0.30	3.450
TOTAL	210			500.87

Am
JE 12/10/20

13
10/10/20
AE

Am
EE 12-10-20