

Inspection Report for Flood damage work

Date:

1. Name of PIUs-

EE RWD (W) division, Mardaur

2. Name of Block/Road-

- Panapur

A. For Road

Motorable of Road from Bijauli
to Bijauli

1. Damage Location/Chainage :

: - 524 M

2. Damage Length

3. Nature of Damage

:

cut in Road, Ducts Flo-2 & 3 run

4. Details of Restoration

i Material being used in Restoration

: Bricks Bats

ii Equipment/Tools being used in Restoration works:

: Tector, Roller

iii Procedure taken up in Restoration works

: - Bricks Bat

iv Restored Length

: 524 M

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length

3. Nature of Damage

4. Details of Restoration

i Material being used in Restoration

:

ii Equipment/Tools being used in Restoration works:

:

iii Procedure taken up in Restoration works

:

iv Restored Length

:

Signature of JE/AE/EE

21-11-2020

21/11/20

Signature

(Name of Inspector)



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

Works Division-Marhaura

FDR

(2020-2021)

NAME OF WORK	Motorable of Road From Bijauli To Bijauli		
DISTRIC	Saran		
BLOCK	Panapur		
LENGTH OF ROAD	3.820	KM	
ESTIMATED COST	50.435	Lac	

FDR

GENERAL ABSTRACT OF COST


Block:-Panapur

District:- Saran

Length of Road:-- 3.820 KM

Name of Road:-- Motorable of Road From Bijauli To Bijauli

SL. No.	Amount
A ESTIMATED COST	: 50.435 Lacs
TOTAL	: 50.435 Lacs


4-12-2020
Junior Engineer


04/12/2020
Asstt. Engineer



Executive Engineer

Technically approved for Rs 50.43500 :- (Fifty lakh forty three thousand five hundred only)


4-12-20
अधीक्षक अभियंता
RWD
ग्रामीण कार्य विभाग
कार्य अंचल, छपरा

Name Of Road :-		Motorable of Road From Bijauli To Bijauli		Block:-	Panapur
Sl. No.	Description	UNIT	QUANTITY	RATE	AMOUNT (in Rs.)
1	Providing Brick Bats				
	Providing brick bats including spreading laying, Labour for dry graded jhama khoa folter under Brick Pitching or boulder pitching in slope or apron including light ramming etc. All complete job as per approved design specification and direction of E/I, including carriage cost of bricks.				
	Quantity As Per Annexure-1	CUM	2342.00	2153.51	5043520.00
				TOTAL COST =	5043520.00

50.43 420.00


4.12.2020
JE
RWD


04/12/2020
AE
RWD


4/12/20
EE
RWD

ANNEXTURE-1

Name Of Road :- Motorable of Road From Bijauli To Bijauli

Block:- Panapur

Sl. No.	Description	Nos.	LENGTH (m)	WIDTH (m)	HEIGHT (m)	UNIT	QUANTITY
	1st Time Flood						
1	CH-1.400 km	1	18.00	2.00	1.50	CUM	54.00 m3
2	CH-1.400 km	1	7.00	2.50	1.50	CUM	26.25 m3
3	CH-1.400 km	1	10.00	0.60	0.50	CUM	3.00 m3
4	CH-1.500 km	1	25.00	1.00	1.25	CUM	31.25 m3
5	CH-1.600 km	1	20.00	5.00	2.50	CUM	170.00 m3
6	CH-1.600 km	1	35.00	5.50	2.50	CUM	250.00 m3
7	CH-1.700 km	1	32.00	4.00	1.50	CUM	480.00 m3
8	CH-1.750 km	1	10.00	4.50	1.50	CUM	192.00 m3
9	CH-1.750 km	1	7.00	1.00	1.50	CUM	67.50 m3
10	CH-1.750 km	1	15.00	2.00	1.50	CUM	10.50 m3
11	CH-1.780 km	1	25.00	2.00	1.50	CUM	45.00 m3
12	CH-1.780 km	1	6.00	4.50	1.75	CUM	75.00 m3
13	CH-1.780 km	1	20.00	1.50	1.00	CUM	47.25 m3
14	CH-1.780 km	1	15.00	1.50	1.00	CUM	30.00 m3
15	CH-1.780 km	1	5.00	2.00	1.00	CUM	22.50 m3
16	CH-1.800 km	1	20.00	1.20	1.25	CUM	10.00 m3
17	CH-1.800 km	1	10.00	1.00	1.00	CUM	30.00 m3
18	CH-2.100 km	1	25.00	1.25	1.00	CUM	10.00 m3
19	CH-2.300 km	1	15.00	1.25	1.00	CUM	31.25 m3
20	CH-3.400 km	1	20.00	5.00	2.50	CUM	18.75 m3
21	CH-3.450 km	1	15.00	1.50	1.00	CUM	250.00 m3
22	CH-3.450 km	1	5.00	1.00	1.00	CUM	22.50 m3
23	CH-3.450 km	1	30.00	1.00	1.50	CUM	5.00 m3
24	CH-3.700 km	1	32.00	1.00	1.00	CUM	45.00 m3
25	CH-3.700 km	4	5.00	1.00	1.00	CUM	32.00 m3
	2nd Time Flood						
1	CH-1.400 km	1	18.00	2.00	1.50	CUM	20.00 m3
2	CH-1.400 km	1	7.00	2.50	1.50	CUM	54.00 m3
3	CH-1.400 km	1	10.00	0.60	0.50	CUM	26.25 m3

Sl. No.	Description	Nos.	LENGTH (m)	WIDTH (m)	HEIGHT (m)	UNIT	QUANTITY
4	CH-1.600 km	1	15.00	5.00	1.50	CUM	112.50 m3
5	CH-1.700 km	1	27.00	5.00	1.75	CUM	236.25 m3
6	CH-3.400 km	1	20.00	5.00	1.00	CUM	100.00 m3
TOTAL QUANTITY =							448.75 m3

2342.00 m³

[Signature]
4.12.2020
JE
RWD

[Signature]
04.12.2020
AE
RWD

[Signature]
EE
RWD