



GOVERNMENT OF BIHAR

NAME OF WORK :- Restoration work of aproach Road for HL bridge over gaurihar man river near brahmsthan gaurihar

(FDR PART-A)

Restoration Length :- 0.042 km

Block:- Sakra

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 384,200.00

**-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST I**

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- MUZAFFARPUR EAST-1
- 2 Name of Block/Road- SAKRA/ Restoration of Approach road for the Bridge over gaunihar Man silver brahmasthan lake

A For ~~Road~~ Bridge.

- 1 Damage Location/Chainage Approach road damaged at many places.
- 2 Damage Length (0.042 km) Multiple reach damaged (0.42 km)
- 3 Nature of Damage side slope & crest damaged
- 4 Details of Restoration Works-

- i Material being used in Restoration Works- Sand Bag, Bamboo pile & Brick Bat etc.
- ii Equipments/Tools being used in Restoration Works- Buldo, Tractor, Manual labor
- iii Procedure Taken up in Restoration Works- Immediate restoration of roadway for traffic restoration.
- iv Restored Length 0.042 KM.

B. For Bridge ✓

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length

Signature of JE/ AE/ EE

Signature
(Name of Inspector)

प्रतिवेदन

कार्य का नाम:- पट्टा पथ (344 लकीरवाला जोरी एर मन) बहालान जोरी एर
के निरुद्ध पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में
यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- लहरा
वित्तीय वर्ष - 2020-21
प्राक्कलित राशि - Rs. 384200

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 384200/- है, कार्य-पट्टा पथ
लहरा-पट्टा पथ प्रखण्ड-लहरा में यातायात बहाली हेतु आपातकालीन मरम्मत के
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा
दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में बाध, बाध जोरी, डे डुका भरकर पथ को चालू
करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी
घटनोत्तर स्वीकृति अपेक्षित है।

अ. उ. ग. क. क.
कनीय अभियंता
सि. क.

अ. उ. ग. क. क.
सहायक अभियंता
01/12/20

अ. उ. ग. क. क.
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुज0
पूर्वी-1

NAME OF WORK:- Restoration work of approach Road for HL bridge over gaurihar man river near brahmsthan gaurihar

Total Length :- 471m (span 20m x 3 Nos)

Restoration Length :- 0.042 km

ABSTRACT OF COST

Sl. No.		Unit	Rates	Quantity	Amount
1	Providing and Laying of Brick Bats: Placing tractor at loading point loading with front end loader dumpong, turning for return trip exluding time for haulage and return trip	Cum	1,768.60	155.07	274,257.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	358.25	17,698.00
3	providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification and direction of E/I	Rm	26.40	52.00	1,373.00
4	Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	860.00	31,132.00
Total Amount					Rs. 324,460.00
Add for GST @ 12%					Rs. 38,935.00
Add for Labour Cess @ 1%					Rs. 3,245.00
Add for Seigniorage Fee					Rs. 17,533.00
Gross Total Amount					Rs. 384,173.00
Say					Rs. 384,200.00

01/12/2020

J.E.
K.R.

01/12/20
A.E.

RWD, Sub-Division, Sakra

01/12/20

Executive Engineer
RWD(W) Div.Muzaffarpur East 1

Technically Approved for Rs. 384200=rs (Three Lac Eighty four Thousand Two hundred) only.

01/12/20
S.E., RWD.
MUZAFFARPUR CIRCE
27/12/20