



GOVERNMENT OF BIHAR

**NAME OF WORK :- Restoration work of Road from Rampur
Bahdsan to Raja Pakar**

(FDR PART-A)

Restoration Length :- 0.30 km

Block:- Sakra

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 611,400.00

**-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST 1**

Inspection Report for Flood Damage Work

Date

1. Name of PIUs- E.E, R.W.D, MUZAFFARPUR EAST-1
2. Name of Block/Road- Salcoo | Rampur Bahdan to Raja Pakkar

A. For Road

1. Damage Location/Chainage : Multiple location heavy damage to shoulder & embankment.
2. Damage Length : 0.300 KM
3. Nature of Damage : Portion of embankment & shoulder damaged at multiple locations.
4. Details of Restoration Works-
 - i. Material being used in Restoration Works- Brick Bat, Sand Bag & Bamboo piling.
 - ii. Equipments/Tools being used in Restoration Works- Tractor, GCB, Roller - manual means -
 - iii. Procedure Taken up in Restoration Works- Immediately Restoration work for opening traffic taken up
 - iv. Restored Length : 0.300 KM

B. For Bridge

1. Damage Location/Chainage
2. Damage Length
3. Nature of Damage
4. Details of Restoration Works-
 - i. Material being used in Restoration Works-
 - ii. Equipments/Tools being used in Restoration Works-
 - iii. Procedure Taken up in Restoration Works-
 - iv. Restored Length

Signature of JE/ AE/ PE

Signature
(Name of Inspector)

प्रतिवेदन

कार्य का नाम:- रामपुर मसौन से राजापकड

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- सकरा

वित्तीय वर्ष - 2020-21

प्राक्कलित राशि - Rs. 611400/- (छह लाख चारह हजार चार सौ ०० मात्र)

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 611400/- है, बन पुर मुजफ्फरपुर पथ-1, प्रखण्ड- सकरा में यातायात बहाली हेतु आपातकालिन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में वालुपेरी, बरत, ईट डुक्का भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।

61.12.20
कनीय अभियंता
सकरा

61.12
सहायक अभियंता

61.12.20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुज0
पूर्वी-1

NAME OF WORK:- Restoration work of Road from Rampur Bahdsan to Raja Pakar

Total Length :-

1.25 Km

Restoration Length :- 0.30 Km

ABSTRACT OF COST

Sl. No.		Unit	Rates	Quantity	Amount
1	Providing and Laying of Brick Bats: Placing tractor at loading point loading with front end loader dumpong, turning for return trip exluding time for haulage and return trip	Cum	1,768.60	208.81	369,301.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	302.50	14,944.00
3	Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	3,700.00	133,940.00
	Total Amount			Rs.	518,185.00
	Add for GST @ 12%			Rs.	62,182.00
	Add for Labour Cess @ 1%			Rs.	5,182.00
	Add for Seigniorage Fee			Rs.	25,839.00
	Gross Total Amount			Rs.	611,388.00
	Say			Rs.	611,400.00

Kam
21/12/20
J.E.

A.E.
A.E. 01/12
RWD, Sub-Division, Sakra

Executive Engineer
Executive Engineer
RWD(W) Div. Muzaffarpur East 1

*Technically approved for Rs. 611400 = -
(Rupees Six Lac Eleven thousand four hundred) only.*

S.E. , RWD (W)
S.E. , RWD (W)
MUZAFFARPUR CIRCLE
27/12/20