

MBND-2544



**GOVERNMENT OF BIHAR**

**NAME OF WORK :- Sarvodaya high school Vishunpur  
Baghnagri se Sonar tola jhitkahi**

**(FDR PART-A)**

**Restoration Length :- 0.175 km**

**Block:- Sakra**

**DETAILED PROJECT REPORT**

**UNDER FDR (2245)**

**ESTIMATED COST**

**Rs. 7,35,100.00**

**:- PREPARED BY :-  
EXECUTIVE ENGINEER  
J. D. (W) DIVISION  
MUSAFFARPUR EAST 1**

प्रतिवेदन

कार्य का नाम - सर्वोच्च एवं उच्च विद्युत वधार्थ  
सिंहार रीला सिंक्रायल पथ में अप्रत्याशित बाढ़ / अतिवृष्टि 2020 से क्षतिग्रस्त पथ में  
यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रकल्प - सिंहार  
वित्तीय वर्ष - 2020-21  
प्राक्कलित राशि - Rs. 735/00 -

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 735/00 = - है,  
प्रकल्प - सिंहार में यातायात बहाली हेतु आपातकालीन मरम्मत के  
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा  
दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में बाढ़ नदी, अतिवृष्टि, बांध भरकर पथ को चालू  
करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चालू अनुसूचित दर पर तैयार किया गया है। इसकी  
घटनोत्तर स्वीकृति अपेक्षित है।

अभियंता  
12/12/20

कनीय अभियंता

सहायक अभियंता  
12/12/20

सहायक अभियंता

कार्यपालक अभियंता  
12/12/20  
ग्रामीण कार्य विभाग  
कार्य प्रबंधन मुजरा  
पूर्वी - 1

## Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- MU2 Harpur East-1
- 2 Name of Block/Road- Sakra / Sarvoday High school / Vishunpur  
Bagnagri se sonar tola, Jhikkahi

### A For Road

- 1 Damage Location/Chainage Multiple Location damaged (0-2.11km)
- 2 Damage Length 0.175km
- 3 Nature of Damage should & Embankment & Curst
- 4 Details of Restoration Works-
  - i Material being used in Restoration Works- Bricks Ball, Sand bag, Bamboo Pile
  - ii Equipments/Tools being used in Restoration Works- Roller, Tractor, Manual
  - iii Procedure Taken up in Restoration Works- Immediate Rerestoration Traffic opening
  - iv Restored Length 0.175km

### B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
  - i Material being used in Restoration Works-
  - ii Equipments/Tools being used in Restoration Works-
  - iii Procedure Taken up in Restoration Works-
  - iv Restored Length

Signature of JE/ AE/ EE

Signature  
(Name of Inspector)



**NAME OF WORK:-** Sarvodaya high school Vishunpur Baghnagri se Sonar tola  
jhirkahi

Total Length :- 2.11 km

Restoration Length :- 0.175 km

**ABSTRACT OF COST**

Sl. No.		Unit	Rates	Quantity	Amount
1	<b>Providing and Laying of Brick Bats:</b> Placing tractor at loading point loading with front end loader dumpong, turning for return trip exluding time for haulage and return tirp	Cum	1,768.60	292.63	5,17,545.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	1,237.00	61,108.00
3	Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	1,167.00	42,245.00
<b>Total Amount</b>					<b>Rs. 6,20,898.00</b>
Add for GST @ 12%					Rs. 74,508.00
Add for Labour Cess @ 1%					Rs. 6,209.00
Add for Seigniorage Fee					Rs. 33,519.00
<b>Gross Total Amount</b>					<b>Rs. 7,35,134.00</b>
<b>Say</b>					<b>Rs. 7,35,100.00</b>

*Abhinit Kumar*  
J.E. 12/12/20

*[Signature]*  
A.E. 12/12/20  
RWD, Sub-Division, Sakra

*[Signature]*  
12-12-20  
Executive Engineer  
RWD(W) Div. Muzaffarpur East 1

Technically approved for Rs. 735100/-  
(Rupees Seven Lac thirty five thousand One hundred) only

*[Signature]*  
12-12-20  
S.E., RWD (W)

MUZAFFARPUR CIRCLE  
29/12/20