

12/5/23



GOVERNMENT OF BIHAR

NAME OF WORK :- Restoration work of Road from Rampur

Rajil Urf Banjriya to Gahampur Koruml

(FDR PART-A)

Restoration Length :- 1.5km

Block:- Sakra

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 1,028,000.00

PREPARED BY :-

EXECUTIVE ENGINEER

R.W.D. (W) DIVISION

MUZAFFARPUR EAST I

Inspection Report for Flood Damage Work

Date

- 1 Name of PUs- Muz (Kear) Road
- 2 Name of Block/Road- Rambur Rdjurf Banjar 1979 RT-RTU Kewad

A For Road

- 1 Damage Location/Chainage Multiple Location damaged (0-6.50 km)
- 2 Damage Length 1.50 km
- 3 Nature of Damage - Crust & Boulder & near crest
- 4 Details of Restoration Works:
 - i Material being used in Restoration Works - Bricks 1200
 - ii Equipments/Tools being used in Restoration Works- Roller & tractor manual
 - iii Procedure Taken up in Restoration Works- 1 mm & 1/2 inch restoration of road way traffic opening
 - iv Restored Length - 1.50 km

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works:
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length

Signature of JE/ AE/ BE

(Name of Inspector)

प्रतिवेदन

कार्य का नाम- शामपुर डागी के बांधारिया के स्तनपुर केपल

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।


प्रकल्प- स्वर्ण
वित्तीय वर्ष - 2020-21
प्रकल्पित राशि - Rs. 1028000=00 (दस लाख अठ्ठाईस हजार (00 गाज)

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि रु. 1028000 है, बांधारिया केपल में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521. दिनांक 05.08.2020 द्वारा भ्रष्टे गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में ई-250 ड्रिफ्टिंग करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चालू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।


कनीय अभियंता


सहायक अभियंता


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुजफ्फर
पूर्वी-1.

NAME OF WORK:- Restoration work of Road from Rampur Raji Urf Banjriya
Ratanpurkewal

Total Length :- 6.5km

Restoration Length :- 1.5km

ABSTRACT OF COST

Sl. No.		Unit	Rates	Quantity	Amount
1	Providing and Laying of Brick Bats: Placing tractor at loading point loading with front end loader dump, turning for return trip exluding time for haulage and return trip	Cum	1,768.60	489.47	865,677.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	-	-
3	Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	-	-
	Total Amount			Rs.	865,677.00
	Add for GST @ 12%			Rs.	103,881.00
	Add for Labour Cess @ 1%			Rs.	8,657.00
	Add for Seigniorage Fee			Rs.	49,779.00
	Gross Total Amount			Rs.	1,027,994.00
	Say			Rs.	1,028,000.00

[Signature]
6/12/20
J.E.

[Signature]
A.E.
RWD, Sub-Division, Sakra

[Signature]
8/12/20
Executive Engineer
RWD(W) Div.Muzaffarpur East 1

Technically approved for Rs. 1,028,000.00
(Rupees Ten Lac twenty Eight thousand) only.

[Signature]
18/12/20
S.E., RWD(W)
MUZAFFARPUR CIRCLE
[Signature]
27/12/20