

MB No 2543

11



## GOVERNMENT OF BIHAR

NAME OF WORK :- Restoration work of Road from Chandni  
Chauk of Sabha Jahagirpur R.C.D road to Muzffarpur Pusa  
R.C.D. road  
(FDR PART-A)

Restoration Length :- 0.2 KM

Block:- Sakra

### DETAILED PROJECT REPORT

UNDER FDR (2245)

### ESTIMATED COST

Rs. 473,600.00

:- PREPARED BY :-  
**EXECUTIVE ENGINEER**  
R.W.D. (W) DIVISION  
MUZAFFARPUR EAST I

### Inspection Report for Flood Damage Work

Date

1 Name of PIUs- Muzaffarpur EAST-1

2 Name of Block/Road- Sakra/ Chandni chaur to sabhajahagir/ R.C.D. road to Muzaffarpur Pusa road etc

A For Road

1 Damage Location/Chainage Multiple location damaged (0-6.2 KM)

2 Damage Length 0.200 KM

3 Nature of Damage crust, shoulder, near culvert breach

4 Details of Restoration Works-

i Material being used in Restoration Works- Brick Bat, Sand Bag, Bamboo piling,

ii Equipments/Tools being used in Restoration Works- Roller, Tractor, Manual Immediate restoration of road way for traffic opening

iii Procedure Taken up in Restoration Works-

iv Restored Length 0.200 KM

B. For Bridge

1 Damage Location/Chainage

2 Damage Length

3 Nature of Damage

4 Details of Restoration Works-

i Material being used in Restoration Works-

ii Equipments/Tools being used in Restoration Works-

iii Procedure Taken up in Restoration Works-

iv Restored Length

Signature of JE/ AE/ EE

Signature  
(Name of Inspector)

## प्रतिवेदन

कार्य का नाम:- चौदनी चौक से सबडा जहागीर पुर डारवसीडी  
रोड मुजफ्फरपुर पुसा रोड तक पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में  
यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।


प्रखण्ड- सकरा


वित्तीय वर्ष - 2020-21


प्राक्कलित राशि - Rs. 4,73,600/- (चार लाख तिहतर हजार रुपये) मात्र

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 4,73,600/- है, क्रा० प्र० मुजफ्फरपुर  
पूर्वी-1, प्रखण्ड- सकरा में यातायात बहाली हेतु आपातकालिन मरम्मत के  
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा  
दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में ईट काटकर सिमेंट कोर मरकर पथ को चालू  
करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी  
घटनोत्तर स्वीकृति अपेक्षित है।

  
01.12.20  
कनीय अभियंता

  
01.12.20  
सहायक अभियंता

  
01.12.20  
कार्यपालक अभियंता  
ग्रामीण कार्य विभाग  
कार्य प्रमंडल मुज०  
पूर्वी-1



**NAME OF WORK:-** Restoration work of Road from Chandni Chauk of Sabha Jahagirpur R.C.D road to Muzffarpur Pusa R.C.D. road

Total Length :-

6.20

Restoration Length :- 0.2 KM

**ABSTRACT OF COST**

| Sl. No. |   | Unit | Rates    | Quantity   | Amount            |
|---------|---|------|----------|------------|-------------------|
| 1       | <b>Providing and Laying of Brick Bats:</b><br>Placing tractor at loading point loading with front end loader dumpoing, turning for return trip exluding time for haulage and return trip                      | Cum  | 1,768.60 | 120.59     | 213,275.00        |
| 2       | Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.  | Rm   | 49.40    | 542.50     | 26,800.00         |
| 3       | Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I | Nos  | 36.20    | 4,500.00   | 162,900.00        |
|         | <b>Total Amount</b>   |      |          | <b>Rs.</b> | <b>402,975.00</b> |
|         | Add for GST @ 12%   |      |          | <b>Rs.</b> | <b>48,357.00</b>  |
|         | Add for Labour Cess @ 1%  |      |          | <b>Rs.</b> | <b>4,030.00</b>   |
|         | Add for Seignoirage Fee   |      |          | <b>Rs.</b> | <b>18,215.00</b>  |
|         | <b>Gross Total Amount</b>   |      |          | <b>Rs.</b> | <b>473,577.00</b> |
|         | <b>Say</b>  |      |          | <b>Rs.</b> | <b>473,600.00</b> |

*[Signature]*  
01/12/20

J.E.

*[Signature]*  
A/E 01/12/20

RWD, Sub-Division, Sakra

*[Signature]*  
8-12-20

Executive Engineer

RWD(W) Div.Muzaffarpur East 1

Technically approved for Rs. 473600 = -

(Rupees four lac. Seventy three thousand six hundred) only.

*[Signature]*  
28.12.20  
S.E., RWD (W)

MUZAFFARPUR, CIRCLE

*[Signature]*  
27/12/20