

MB/16 - 2365



**GOVERNMENT OF BIHAR**

**NAME OF WORK :- Restoration work of Road from MMGSY  
sadak se chintawanpur aghwara kadane nadi tak**

**(FDR PART-A)**

**Restoration Length :- 0.042km**

**Block:- Sakra**

**DETAILED PROJECT REPORT**

**UNDER FDR (2245)**

**ESTIMATED COST**

**Rs. 1,76,300.00**

**-: PREPARED BY :-  
EXECUTIVE ENGINEER  
R.W.D. (W) DIVISION  
MUZAFFARPUR EAST 1**

## Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- MUZAFFARPUR EAST-1
- 2 Name of Block/Road- SAKRA) MM45Y sadak se chintawanpur  
Aghwara Kodane nadi tak

A For Road

- 1 Damage Location/Chainage many places (0 - 0.783 KM)
- 2 Damage Length 0.042 KM
- 3 Nature of Damage Breach in embankment <sup>exists</sup> shoulder damaged
- 4 Details of Restoration Works-
  - i Material being used in Restoration Works- Brick Bat & sand bag with bamboo piling
  - ii Equipments/Tools being used in Restoration Works- Tractor, Roller, trolley etc manual labour
  - iii Procedure Taken up in Restoration Works- Immediate restoration work for resuming traffic operation.
  - iv Restored Length : 0.042 KM (42 m).

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
  - i Material being used in Restoration Works-
  - ii Equipments/Tools being used in Restoration Works-
  - iii Procedure Taken up in Restoration Works-
  - iv Restored Length

Signature of JE/ AE/ EE

Signature  
(Name of Inspector)

प्रतिवेदन

कार्य का नाम:- Restoration work of Road from MMGSY Sadak  
to Chintanpur, Ashwara, Kachanpur में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में  
यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- सकरा  
वित्तीय वर्ष - 2020-2021  
प्राक्कलित राशि - Rs. 176300/- (एक लाख सैंटन एजार तीन सैं मत्स)

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 176300/- है, One lakh Seventy  
Six thousand Three hundred Only प्रखण्ड- सकरा में यातायात बहाली हेतु आपातकालिन मरम्मत के  
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521. दिनांक 05.08.2020 द्वारा  
दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bat, Sand Bag भरकर पथ को चालू  
करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चालू अनुसूचित दर पर तैयार किया गया है। इसकी  
घटनोत्तर स्वीकृति अपेक्षित है।

31/12/20  
01.12.2020  
कनीय अभियंता  
सकरा-1

01/12/20  
सहायक अभियंता,

01/12/20  
कार्यपालक अभियंता  
ग्रामीण कार्य विभाग  
कार्य प्रमंडल मुज0  
पूर्वी-1.

**NAME OF WORK:-** Restoration work of Road from MMGSY sadak se chintawanpur aghwara kadane nadi tak

Total Length :- 0.783km

Restoration Length :- 0.042km

**ABSTRACT OF COST**

Sl. No.		Unit	Rates	Quantity	Amount
1	<b>Providing and Laying of Brick Bats:</b> Placing tractor at loading point loading with front end loader dumpung, turning for return trip exluding time for haulage and return tirp	Cum	1,768.60	78.12	1,38,163.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	51.10	2,524.00
3	Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	222.00	8,036.00
<b>Total Amount</b>					<b>Rs. 1,48,723.00</b>
Add for GST @ 12%					Rs. 17,847.00
Add for Labour Cess @ 1%					Rs. 1,487.00
Add for Seigniorage Fee					Rs. 8,288.00
<b>Gross Total Amount</b>					<b>Rs. 1,76,345.00</b>
<b>Say</b>					<b>Rs. 1,76,300.00</b>

31/12/20  
81-12-2020  
J.E. SAKRA

A.E. 21/12/20  
RWD, Sub-Division, Sakra

Executive Engineer  
RWD(W) Div. Muzaffarpur East 1

Technically approved for Rs. 176300/-  
(Rupees One lac Seventy six thousand three hundred) only.

23-12-20  
S.E. RWD (W)

MUZAFFARPUR CIRCLE

21/12/20