



GOVERNMENT OF BIHAR

**NAME OF WORK :- Restoration work of Road from Pipri
Bejha Road to charmukha tola**

(FDR PART-A)

Restoration Length :- 0.2km

Block:- Sakra

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 370,100.00

**-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST 1**

Inspection Report for Flood Damage Work

Date

1. Name of PIUs- M42 Harpur East-1
2. Name of Block/Road- सकरा/पीपरी बेडा सड़क से चरमुखा रोड

A For Road

1. Damage Location/Chainage Multiple Location damaged (0-1.57 km)
2. Damage Length 0.200 km
3. Nature of Damage Near Culvert & shoulder
4. Details of Restoration Works-
 - i. Material being used in Restoration Works- Bricks Bat, sand bag bamboo Pile
 - ii. Equipments/Tools being used in Restoration Works- Roller Tractor manual
 - iii. Procedure Taken up in Restoration Works- Immediate restoration of road way traffic opening
 - iv. Restored Length — 0.200 km

B. For Bridge

1. Damage Location/Chainage
2. Damage Length
3. Nature of Damage
4. Details of Restoration Works-
 - i. Material being used in Restoration Works-
 - ii. Equipments/Tools being used in Restoration Works-
 - iii. Procedure Taken up in Restoration Works-
 - iv. Restored Length

Signature of JE/ AE/ EE

Signature
(Name of Inspector)

प्रतिवेदन

कार्य का नाम:-

पीपरी बेड़ा सड़क से चरमुख रोता

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- सफरा

वित्तीय वर्ष - 2020-21

प्राक्कलित राशि - Rs. - 370100=00 (तीन लाख सत्तर हजार एक सौ 00) मात्र

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 370100=00 है, प्रखण्ड- सफरा में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में ई 2 काटकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।

01/12/20
कनीय अभियंता

01/12
सहायक अभियंता

01/12-20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुज0
पूर्वी-1

NAME OF WORK:- Restoration work of Road from Pipri Bejha Road to charmukha tola

Total Length :- 1.157km

Restoration Length :- 0.2km

ABSTRACT OF COST

Sl. No.		Unit	Rates	Quantity	Amount
1	Providing and Laying of Brick Bats: Placing tractor at loading point loading with front end loader dump, turning for return trip exluding time for haulage and return trip	Cum	1,768.60	99.91	176,701.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	302.50	14,944.00
3	Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	3,400.00	123,080.00
	Total Amount			Rs.	314,725.00
	Add for GST @ 12%			Rs.	37,767.00
	Add for Labour Cess @ 1%			Rs.	3,147.00
	Add for Seigniorage Fee			Rs.	14,441.00
	Gross Total Amount			Rs.	370,080.00
	Say			Rs.	370,100.00

[Signature]
01.12.20
J.E.

[Signature]
A.E. 01/12

[Signature]
8.12
Executive Engineer

RWD, Sub-Division, Sakra

RWD(W) Div.Muzaffarpur East 1

Technically approved for Rs. 370100 = w
(Rupees Three lac seventy thousand one hundred only)

[Signature]
12.12.20
S.E. (RWD(W))

MUZAFFARPUR, CIRCLE.
[Signature]
21/12/20