



GOVERNMENT OF BIHAR

NAME OF WORK :- Restoration work of Road from Mehsi
chouk Vshali Siman to Gannipur Bejha Haat (Middle School)

(FDR PART-A)

Restoration Length :- 10km

Block:- Sakra

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 1,213,300.00

-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST 1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- Muzharpur East - I
- 2 Name of Block/Road- Sakia / Restoration of work Mehsi Chowk Raishali
Siman to Gannipur Begha

A For Road

- 1 Damage Location/Chainage Multiple Location - (0 - 1.765)
- 2 Damage Length (0.600) km
- 3 Nature of Damage embankment damaged due flood crust
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works- Brick Bat, Bamboo Pile, sand bag
 - ii Equipments/Tools being used in Restoration Works- Roller Tractor manual means
 - iii Procedure Taken up in Restoration Works- Immediate Restoration work taken up to completed to restore traffic
 - iv Restored Length - 0.600 km

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length

Signature of JE/ AE/ EE

Signature
(Name of Inspector)

प्रतिवेदन

कार्य का नाम:-

मेसज चोक बहाली खाता से 21.11.20 वृक्ष (मं.वि.)

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- 21331
वित्तीय वर्ष - 2020-21
प्राक्कलित राशि - Rs. 1213300/-

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 1213300/- है, प्रखण्ड- 21331 में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में बाढ़/अतिवृष्टि भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।

अभियंता प्रमुख
01/12

कनीय अभियंता

सहायक अभियंता

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुज0
पूर्वी-1

NAME OF WORK:- Restoration work of Road from Mehshi chouk Vshali Siman to Gannipur Bejha Haat (Middle School)

Total Length :- 1.765km

Restoration Length :- .600km

ABSTRACT OF COST

Sl. No.		Unit	Rates	Quantity	Amount
1	Providing and Laying of Brick Bats: Placing tractor at loading point loading with front end loader dump, turning for return trip excludng time for haulage and return turn	Cum	1,768.60	460.40	814,263.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	412.50	20,378.00
3	Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	5,300.00	191,860.00
	Total Amount			Rs.	1,026,501.00
	Add for GST @ 12%			Rs.	123,180.00
	Add for Labour Cess @ 1%			Rs.	10,265.00
	Add for Seigniorage Fee			Rs.	53,377.00
	Gross Total Amount			Rs.	1,213,323.00
	Say			Rs.	1,213,300.00

Abhishek
01/12
J.E.

Jan
01/12
A.E.
RWD, Sub-Division, Sakra

8.12.20
Executive Engineer
RWD(W) Div.Muzaffarpur East 1

Technically approved for Rs. 1213300 =
(Rupees Twelve lac Thirteen thousand three hundred) only

28.12.20
S.E., RWD(W)
MUZAFFARPUR CIRCLE
27/12/20