



GOVERNMENT OF BIHAR

**NAME OF WORK :- Restoration work of Road from L028
Madrsha Chauk to Mandai khurd**

(FDR PART-A)

Restoration Length :- C 300km

Block:- Sakra

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 970,500.00

**:- PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST 1**

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- MUZ Harpur East-1
- 2 Name of Block/Road- Sakra / L028 Madishachauk to Mandai Khurd.

A For Road

- 1 Damage Location/Chainage Multiple Location^{ch} (0-3.021) km
- 2 Damage Length 0.300 km
- 3 Nature of Damage embankment damaged crust due to flood
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works- Brick bat, Sand bag Bamboo Pile
 - ii Equipments/Tools being used in Restoration Works- Roller Tractor manual
meng
 - iii Procedure Taken up in Restoration Works- Immediate Restoration work taken
up to completed to restore traffic.
 - iv Restored Length - 0.300 km

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length

Signature of JE/ AE/ EE

Signature
(Name of Inspector)

प्रतिवेदन

कार्य का नाम:-

CO28 मईसा चौक से मंडई खुर्द तक

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- सकरा
वित्तीय वर्ष - 2020-21

प्राक्कलित राशि - Rs. 970,500 (नव लाख सतर हजार पाँच सौ ०0) मात्र

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 970,500 = ०0 है, १,१०,५०० मुजफ्फरपुर
पूर्व-1, प्रखण्ड- सकरा में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में डिट कार्ड, आवक, सिमेंट नोच लोच बालू भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।

01/12/20
कनीय अभियंता

01/12/20
सहायक अभियंता

08/12/20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुज0
पूर्व-1

NAME OF WORK:-

Restoration work of Road from L028 Madrsha Chauk to Mandai khurd

Total Length :-

3.021 km

Restoration Length :- 0.300 km

ABSTRACT OF COST

Sl. No.		Unit	Rates	Quantity	Amount
1	Providing and Laying of Brick Bats: Placing tractor at loading point loading with front end loader dumpoing, turning for return trip exluding time for haulage and return tirn	Cum	1,768.60	364.50	644,655.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	495.00	24,453.00
3	Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	4,200.00	152,040.00
	Total Amount			Rs.	821,148.00
	Add for GST @ 12%			Rs.	98,538.00
	Add for Labour Cess @ 1%			Rs.	8,211.00
	Add for Seigniorage Fee			Rs.	42,602.00
	Gross Total Amount			Rs.	970,499.00
	Say			Rs.	970,500.00

[Signature]
01.12.20
J.E.

[Signature]
A.E 01/12/20

[Signature]
8.12.20
Executive Engineer

RWD, Sub-Division, Sakra

RWD(W) Div. Muzaffarpur East 1

Technically approved for Rs 970500 =
(Rupees Nine Lac Seventy thousand five hundred) only.

[Signature]
27.12.20
S.E., RWD(W)
MUZAFFARPUR CIRCLE
[Signature]
27/12/20