



GOVERNMENT OF BIHAR

NAME OF WORK :- Restoration work of Road from Pipri to Gannipur Bejha jane wali Sandak me Serajabad samsan ke nikat

(FDR PART-A)

Restoration Length :- 0.035km

Block:- Sakra

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 307,500.00

:- PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST 1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- M42 (Aspur East-1)
- 2 Name of Block/Road- Sakra / Pipri to Giannipur Beghajane wali sandak me sangibad Samsan Kenikat.

A For Road

- 1 Damage Location/Chainage Multiple Location damaged (0-4.00 km)
- 2 Damage Length 0.085 km
- 3 Nature of Damage near culvert & shoulder
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works- Brick bats
 - ii Equipments/Tools being used in Restoration Works- Roller Tractor, manual
 - iii Procedure Taken up in Restoration Works- Immediate restoration of road way traffic opening
 - iv Restored Length — 0.085 km

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length

Signature of JE/ AE/ EE

Signature
(Name of Inspector)

प्रतिवेदन


कार्य का नाम:- पीपरी से गन्नीपुर बेड़ा जाने वाली सड़क में सिराजाबाद
शमशान के निकट पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में
यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।


प्रखण्ड- सफरा
वित्तीय वर्ष - 2020-21
प्राक्कलित राशि - Rs. 307500/- (तीन लाख सात हजार पाँच सौ २००) मात्र-

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 307500/- है, पत्रांक 2521
पूर्वी-1, प्रखण्ड-सफरा में यातायात बहाली हेतु आपातकालीन मरम्मत के
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521, दिनांक 05.08.2020 द्वारा
दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में ईट का दुरुस्ती भरकर पथ को चालू
करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी
चटनोत्तर स्वीकृति अपेक्षित है।


कनीय अभियंता


सहायक अभियंता,


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुजफ्फर
पूर्वी-1.

NAME OF WORK:-**Restoration work of Road from Pipri to Gannipur Bejha Jane wall Sandak me Serajabad samsan ke nilkat .**


Total Length :- 4.00km

Restoration Length :- 0.035km

ABSTRACT OF COST

	Unit	Rates	Quantity	Amount
Providing and Laying of Brick Bats:				
Placing tractor at loading point loading with front end loader dumpong, turning for return trip exluding time for haulage and return time	Cum	1,768.60	146.40	258,923.00
Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	-	-
Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	-	-
Total Amount			Rs.	258,923.00
Add for GST @ 12%			Rs.	31,071.00
Add for Labour Cess @ 1%			Rs.	2,589.00
Add for Seigniorage Fee			Rs.	14,889.00
Gross Total Amount			Rs.	307,472.00
Say			Rs.	307,500.00


J.E.
01.12.20


A.E.
RWD, Sub-Division, Sakra


Executive Engineer
RWD(W) Div.Muzaffarpur East 1

Technically approved for Rs. 307500=-
(Rupees three lac Seven thousand five hundred) only.


S.E., RWD (W)

MUZAFFARPUR CIRCLE
27/12/20