



GOVERNMENT OF BIHAR

Bharthipur
NAME OF WORK :- Restoration work of Road From Mundiari
to Ganiyari

(FDR PART-A)

Restoration Length :- 0.271 Km

Block:- Sakra

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 17.79,900.00

-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST I

Inspection Report for Flood Damage Work

Date

1. Name of PIUs- Muzaffarpur East-1
2. Name of Block/Road- SAKRAI Restoration of road from
Bharthipur Mudiyan to garhiyan

A. For Road

1. Damage Location/Chainage Multiple location heavy ditch formed
& side damaged in (0 - 3.923 km)
2. Damage Length 0.271 KM
3. Nature of Damage embankment damaged due to flood from kadane
nadi
4. Details of Restoration Works-
 - i. Material being used in Restoration Works- Pick Bad Bamboo piling &
sand bags.
 - ii. Equipments/Tools being used in Restoration Works-
Roller, Tractor, manual means -
 - iii. Procedure Taken up in Restoration Works- Immediate Restoration
work taken up & completed to restore traffic
 - iv. Restored Length 0.271 KM.

B. For Bridge

1. Damage Location/Chainage
2. Damage Length
3. Nature of Damage
4. Details of Restoration Works-
 - i. Material being used in Restoration Works-
 - ii. Equipments/Tools being used in Restoration Works-
 - iii. Procedure Taken up in Restoration Works-
 - iv. Restored Length

Signature of JE/ AE/ EE

Signature
(Name of Inspector)

प्रतिवेदन

कार्य का नाम:- राबपुर मुडियारी व राबपुरी पथ

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- राबपुर
वित्तीय वर्ष - 2020-21
प्राक्कलित राशि - Rs. 17,79,900/- (सतरह लाख अठ्ठासी हजार नौ सौ मात्र)

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 17,79,900/- है, कट-40
प्रखण्ड- राबपुर में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521, दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में इन्टरलॉक, बस, गलकी भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।

अभि. प्र. को.
कनीय अभियंता 12.2020
सहायक अभियंता
01/12/20

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुज0
पूर्वी-1

NAME OF WORK:- Restoration work of Road From ^{Bharthi pur} Mundiari to Ganiyari

Total Length :- 3.923 Km

Restoration Length :- 0.271 Km

ABSTRACT OF COST

	Unit	Rates	Quantity	Amount
Providing and Laying of Brick Bats:				
Placing tractor at loading point loading with front end loader dump, turning for return trip exluding time for haulage and return trip	Cum	1,768.60	837.23	14,80,725.00
Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	228.15	11,271.00
Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	198.00	7,168.00
Total Amount			Rs.	14,99,164.00
Add for GST @ 12%			Rs.	1,79,900.00
Add for Labour Cess @ 1%			Rs.	14,992.00
Add for Seigniorage Fee			Rs.	85,821.00
Gross Total Amount			Rs.	17,79,877.00
Say			Rs.	17,79,900.00

J.E.
01/12/20
01.12.2020

A.E.
01/12/20
RWD, Sub-Division, Sakra

Executive Engineer
RWD(W) Div. Muzaffarpur East 1

Technically approved for Rs. 1779900=-
(Rupees Seventy Lac
(Rupees Seventeen Lac Seventy Nine thousand Nine hundred) only.

S.E. RWD(W)

MUZAFFARPUR CIRCLE
27/12/20