

MB No. 2519

①



GOVERNMENT OF BIHAR

**NAME OF WORK :- Restoration work of Road from L050 sakra
bazid se mushahari**

(FDR PART-A)

Restoration Length :- .300km

Block:- Sakra

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 754,900.00

**-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST 1**

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- Muzharpur East-1
- 2 Name of Block/Road- Sakra / Lo50 Sakra Bazid to Mushkahari

A For Road

- 1 Damage Location/Chainage - Multiple Location damaged (0 - 1300km)
- 2 Damage Length 0.300 km
- 3 Nature of Damage ~~Multiple Location damaged~~ (Near ^{Culvert} Shoulder)
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works- Bricks bats, Sand bag, bamboo Pile
 - ii Equipments/Tools being used in Restoration Works- ~~Bricks Bat, Sand bag~~ Tractor manual
 - iii Procedure Taken up in Restoration Works- Immediate Re restoration traffic opening
 - iv Restored Length → 0.300 km.

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length

Signature of JE/ AE/ EE

Signature
(Name of Inspector)

प्रतिवेदन

कार्य का नाम:-

1050 सकरा बाजिद से मुसहरी

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड-

सकरा

वित्तीय वर्ष -

2020-21

प्राक्कलित राशि - Rs.

754900/-

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि

754900/-

है,

मसहरी-84-1

प्रखण्ड-

सकरा

लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521, दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में बाधारी, 9/8, 32 555 भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।

01.12.20

कनीय अभियंता

9/11

सहायक अभियंता,

4.12.20

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुज0
पूर्वी-1

ME OF WORK:-

Restoration work of Road from Lo 50 Sakra Bazid to Musbahri

Total Length :- 1.200km

Restoration Length :- .300km

ABSTRACT OF COST

	Unit	Rates	Quantity	Amount
Providing and Laying of Brick Bats:				
Placing tractor at loading point loading with front end loader dumpong, turning for return trip excludng time for haulage and return trip	Cum	1,768.60	278.09	491,830.00
Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	412.50	20,378.00
Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	3,500.00	126,700.00
Total Amount			Rs.	638,908.00
Add for GST @ 12%			Rs.	76,669.00
Add for Labour Cess @ 1%			Rs.	6,389.00
Add for Seigniorage Fee			Rs.	32,893.00
Gross Total Amount			Rs.	754,859.00
Say			Rs.	754,900.00

J.E.
01/12/20

A.E.
RWD, Sub-Division, Sakra

Executive Engineer
RWD(W) Div.Muzaffarpur East 1

Technically approved for Rs. 754900=-w
(Seven Lac fifty four thousand nine hundred) only.

S.E., RWD (W)

MUZAFFARPUR CIRCLE
25/12/20