



GOVERNMENT OF BIHAR

**NAME OF WORK :- Restoration work of Road from T02 TO
Gnipur bhejha**

(FDR PART-A)

Restoration Length :- 0.5km

Block:- Sakra

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 2,173,300.00

**-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST 1**

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- MUZAFFARPUR East-1
- 2 Name of Block/Road- SAKRA/ TO2 to gannipur Bejha

A For Road

- 1 Damage Location/Chainage Multiple Location heavy ditch (0-2.496
- 2 Damage Length 0.500 km
- 3 Nature of Damage Crust, embankment shoulder
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works- Brick bat, Bamboo Pile
sand bag
 - ii Equipments/Tools being used in Restoration Works- Roller, Tractor, JCB,
manual means.
 - iii Procedure Taken up in Restoration Works- Immediate Restoration work
taken up to completed to restore traffic.
 - iv Restored Length - 0.500 km

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length

Signature of JE/ AE/ EE

Signature
(Name of Inspector)

प्रतिवेदन

कार्य का नाम:-

T02 से 21 नवंबर 2020 तक

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- ~~LMR~~

वित्तीय वर्ष - 2020-21

प्राक्कलित राशि - Rs. 2173,300/-

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 2173300/- है, प्रखण्ड- ~~LMR~~ में यातायात बहाली हेतु आपातकालिन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521, दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में बाधों को हटाने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।

कनीय अभियंता
LMR

सहायक अभियंता

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुजफ्फरपुर
पूर्वी-1

NAME OF WORK:- Restoration work of Road from T02 TO Gnipur bhejha


Total Length :- 2.496 km


Restoration Length :- 0.5km

ABSTRACT OF COST


Sl. No.		Unit	Rates	Quantity	Amount
1	Providing and Laying of Brick Bats: Placing tractor at loading point loading with front end loader dumpoing, turning for return trip exluding time for haulage and return turn	Cum	1,768.60	956.91	1,692,391.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	731.13	36,118.00
3	Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	2,890.00	104,618.00
	Total Amount			Rs.	1,833,127.00
	Add for GST @ 12%			Rs.	219,975.00
	Add for Labour Cess @ 1%			Rs.	18,331.00
	Add for Seigniorage Fee			Rs.	101,915.00
	Gross Total Amount			Rs.	2,173,348.00
	Say			Rs.	2,173,300.00


01.12.20
J.E.


A.E.
RWD, Sub-Division, Sakra


8.12.20
Executive Engineer
RWD(W) Div.Muzaffarpur East 1

Technically approved for Rs. 2,173,300 = —
(Rupees Twenty One lac Seventy three thousand three hundred) only.


27.12.20
S.E., RWD (W)
MUZAFFARPUR CIRCLE
27/12/20