

MBNO - 2561

1



GOVERNMENT OF BIHAR

**NAME OF WORK :- Restoration work of Road sakra
bariyarpur kandh 103 se gaurihar**

(FDR PART-A)

Restoration Length :- 0.220km

Block:- Sakra

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 1,299,200.00

**-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUNICIPALITY ZAFFARPUR EAST 1**

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- EE, MUZAFFARPUR EAST-1
- 2 Name of Block/Road- ~~SHRA~~ BARIYARPUR KANDH TO SE GARIHAR

A For Road

- 1 Damage Location/Chainage : Damage in crust, subgrade & shoulder
- 2 Damage Length : 0.220 KM at multiple reach (0 - 1.12 KM)
- 3 Nature of Damage : SUBGRADE, CRUST & shoulder at multiple locations
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works- Brick Bat, Sand Bag, Bamboo nily-etc.
 - ii Equipments/Tools being used in Restoration Works- Roller, Tractor, etc
 - iii Procedure Taken up in Restoration Works- Immediate restoration
 - iv Restored Length : 0.220 KM work taken up in order to restore traffic

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length

Signature of JE/ AE/ EE

Signature
(Name of Inspector)

प्रतिवेदन

कार्य का नाम:-

अस्थायी बाढ़ रोड/अतिवृष्टि

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड:-

बलिया

वित्तीय वर्ष - 20-21

प्राक्कलित राशि - Rs. 1299200/-

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि

1299200/-

है,

1299200/-

लिए तैयार किया गया है।

प्रखण्ड:- बलिया

में यातायात बहाली हेतु आपातकालीन मरम्मत के

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में यातायात को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चालू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।

01.12.20

कनीय अभियंता

01.12

सहायक अभियंता,

01.12.20

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुज0
पूर्वी-1.

NAME OF WORK:-

Restoration work of Road sakra bariyarpur kandh t03 se gaurihar

Total Length :- 1.120 km

Restoration Length :- 0.220km

ABSTRACT OF COST

	Unit	Rates	Quantity	Amount
Providing and Laying of Brick Bats:				
Placing tractor at loading point loading with front end loader dumping, turning for return trip excludng time for haulage and return trip	Cum	1,768.60	509.36	900,854.00
Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	1,966.88	97,164.00
Providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification and direction of E/I	Rm	26.40	198.00	5,227.00
Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	2,605.00	94,301.00
Total Amount			Rs.	1,097,546.00
Add for GST @ 12%			Rs.	131,706.00
Add for Labour Cess @ 1%			Rs.	10,975.00
Add for Seigniorage Fee			Rs.	59,006.00
Gross Total Amount			Rs.	1,299,233.00
Say			Rs.	1,299,200.00

[Signature]

J.E.

[Signature]
A.E. 01/12

RWD, Sub-Division, Sakra

[Signature]
4.12.20

Executive Engineer

RWD(W) Div.Muzaffarpur East 1

Technically approved for Rs. 1299200-00 (Twelve lac Ninety Nine Thousand Two hundred) only.

[Signature]
28-12-20
SE, RWD.

MUZAFFARPUR CIRCLE
[Signature]
29/12/20