



GOVERNMENT OF BIHAR

NAME OF WORK :- L046 to Kanya vidyalay shera tola tak

(FDR PART-A)

Restoration Length :- 0.232 km

Block:- Sakra

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 7,49,700.00

-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST 1

प्रतिवेदन

कार्य का नाम -

1046 स् कल्या विद्यालय 2/21 रीसा 15

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड -

21425

वित्तीय वर्ष - 2020-21

प्राक्कलित राशि - Rs. 749700/-

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 749700/- है,

प्रखण्ड 21425 में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में बाढ़ की, 2/21 रीसा 15 भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चालू अनुसूचित दर पर तैयार किया गया है। इसकी घटनोत्तर स्वीकृति अपेक्षित है।

कनीय अभियंता

सहायक अभियंता

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रबंधन मुजरा
पूर्वी-1

Inspection Report for Flood Damage Work

Date


- 1 Name of PIUs- Muzaffarpur East-1
- 2 Name of Block/Road- Saksa/ Restoration of road from L046 to Kanya Vidyalaya Shera to Lak


A For Road

- 1 Damage Location/Chainage Multiple Location haenryditeh (0-7.77) Km
- 2 Damage Length 0.232 Km
- 3 Nature of Damage embankment damaged due to flood bank
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works- Brick Bat, Bamboo Pile, Sand bag
 - ii Equipments/Tools being used in Restoration Works- Roller, Tractor, manual means
 - iii Procedure Taken up in Restoration Works- Immediate Restoration work taken up to completed to restore traffic
 - iv Restored Length - 0.232

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length


Signature of JE/ AE/ EE


Signature
(Name of Inspector)

NAME OF WORK:- L046 to Kanya vidyalay shera tola tak

Total Length :- 1.777 km

Restoration Length :- 0.232 km

ABSTRACT OF COST

Sl. No.		Unit	Rates	Quantity	Amount
1	<u>Providing and Laying of Brick Bats:</u> Placing tractor at loading point loading with front end loader dumpong, turning for return trip exluding time for haulage and return tirp	Cum	1,768.60	299.65	5,29,961.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	1,143.75	56,501.00
3	providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification and direction of E/I	Rm	26.40	170.00	4,488.00
4	Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	1,162.00	42,064.00
	Total Amount			Rs.	6,33,014.00
	Add for GST @ 12%			Rs.	75,962.00
	Add for Labour Cess @ 1%			Rs.	6,330.00
	Add for Seignoirage Fee			Rs.	34,400.00
	Gross Total Amount			Rs.	7,49,706.00
	Say			Rs.	7,49,700.00

Abhinita K
12/12/20

J.E.

Jon
A.E 12/12

RWD, Sub-Division, Sakra

[Signature]
12-12-20

Executive Engineer

RWD(W) Div.Muzaffarpur East 1

Technically approved for Rs, 749700.-
(Rupees, Seven Lac forty Nine thousand Seven hundred) only.

[Signature]
12-12-20

S.E., RWD (W)

MUZAFFARPUR CIRCLE

[Signature]
27/12/20