

MB No - 2534



GOVERNMENT OF BIHAR

NAME OF WORK :- Lo69 Ashok singh ke ghar se man gaurihar
tak

(FDR PART-A)

Restoration Length :- 0.168 km

Block:- Sakra

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 7,90,000.00

-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST 1

प्रतिवेदन

कार्य का नाम

1069 31214 सिंके एल एन ऑफिस

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड - 21635

वित्तीय वर्ष - 2020-21

प्राक्कलित राशि - Rs. 790,000/-

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 790,000/- है,

प्रखण्ड - 21635 में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में ड्रडिंग, माफ़िंग, ग्राउन्डिंग और पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी घटनोत्तर स्वीकृति अपेक्षित है।

Ashutosh
12/12/20

कनीय अभियंता

Gen
12/12/20

सहायक अभियंता

12/12/20

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रबंधन मजदूर
पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- MUZAFFARABAD EAST-1
- 2 Name of Block/Road- SAKRA

A For Road

- 1 Damage Location/Chainage embankment & side shoulder
- 2 Damage Length damaged in km (0-0.76 km)
- 3 Nature of Damage 0.168 km
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works- Bagged, Bamboo pile
 - ii Equipments/Tools being used in Restoration Works- Rock Bats
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length

01/24/20
Signature of JE/ AE/ EE

01/24/20
Signature
(Name of Inspector)

NAME OF WORK:- Lo69 Ashok singh ke ghar se man gaurihar tak

Total Length :- 0.76 km

Restoration Length :- 0.168 km

ABSTRACT OF COST

Sl. No.		Unit	Rates	Quantity	Amount
1	Providing and Laying of Brick Bats: Placing tractor at loading point loading with front end loader dump, turning for return trip excludng time for haulage and return trip	Cum	1,768.60	319.26	5,64,643.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	993.88	49,098.00
3	providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification and direction of E/I	Rm	26.40	194.00	5,122.00
4	Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	1,328.00	48,074.00
	Total Amount			Rs.	6,66,937.00
	Add for GST @ 12%			Rs.	80,032.00
	Add for Labour Cess @ 1%			Rs.	6,669.00
	Add for Seigniorage Fee			Rs.	36,321.00
	Gross Total Amount			Rs.	7,89,959.00
	Say			Rs.	7,90,000.00

Ashok Singh
12/11/20
J.E. SAKRA

[Signature]
A.E.
12/11/20
RWD, Sub-Division, Sakra

[Signature]
12.12.20
Executive Engineer
RWD(W) Div.Muzaffarpur East 1

Technically approved for Rs. 790000.00
(Rupees Seven lac Ninety thousand) only.

[Signature]
12.12.20
S.E., RWD(W)

MUZAFFARPUR CIRCLE
[Signature]
27/11/20