



GOVERNMENT OF BIHAR

NAME OF WORK :- Restoration work of Road from Loharna
Pul to Muslim Tola

(FDR PART-A)

Restoration Length :- .45km

Block:- Sakra

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

₹ 227,600.00

-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST 1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- MUZAFFARPUR EAST-
- 2 Name of Block/Road- Sakra / Loharna Pul to Muslim Tola

A For Road

- 1 Damage Location/Chainage - Multiple Location damaged (0-1250km)
- 2 Damage Length 10.450km
- 3 Nature of Damage Near shoulder & Culvert
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works- Brickbat ^{Sand bag & bamboo} _{shaul} pipe
 - ii Equipments/Tools being used in Restoration Works- Tractor manual
 - iii Procedure Taken up in Restoration Works- Immediate Rerestoration traffic opening
 - iv Restored Length - 0.450km

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length


Signature of JE/ AE/ EE


Signature
(Name of Inspector)

प्रतिवेदन

कार्य का नाम— मोहरना पुल से मुस्लिम कोला
पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड— एफएफ
वित्तीय वर्ष— 2020-21
प्राक्कलित राशि— Rs. 927600/-

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 927600/- है, 421422
29/-11, प्रखंड— एफएफ में यातायात बहाली हेतु आपातकालिन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में बाधवादी कार्य करके पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चालू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।

21/12/20
कनीय अभियंता

21/12/20
सहायक अभियंता

21/12/20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुज0
पूर्वी-1

NAME OF WORK:- Restoration work of Road from Loharna Pul to Muslim Tola

Total Length :- 1.25km

Restoration Length :- .45km

ABSTRACT OF COST

Sl. No.		Unit	Rates	Quantity	Amount
1	Providing and Laying of Brick Bats: Placing tractor at loading point loading with front end loader dump, turning for return trip exluding time for haulage and return trip	Cum	1,768.60	331.38	586,079.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	302.50	14,944.00
3	Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	5,100.00	184,620.00
	Total Amount			Rs.	785,643.00
	Add for GST @ 12%			Rs.	94,277.00
	Add for Labour Cess @ 1%			Rs.	7,856.00
	Add for Seigniorage Fee			Rs.	39,816.00
	Gross Total Amount			Rs.	927,592.00
	Say			Rs.	927,600.00

[Signature]
01/12/20
J.E.

[Signature]
A.E 01/12
RWD, Sub-Division, Sakra

[Signature]
4.12.20
Executive Engineer
RWD(W) Div.Muzaffarpur East 1

Technically approved for Rs. 927600= w.
(Rupees Nine Lac Twenty Seven thousand Six hundred only).

[Signature]
28.12.20
S.E., RWD (W)

MUZAFFARPUR CIRCLE.
[Signature]
29/12/20