



GOVERNMENT OF BIHAR

NAME OF WORK :- Restoration work of Road from
Sujawalpur Gannipur Bejha Sandak me Dairy to Machhahi
muslim toia Donma siman Sabha Maricha Road tak
(FDR PART-A)

Restoration Length :- 0.3km

Block:- Sakra

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 596,500.00

-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST 1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- Muzaffarpur Eas
2 Name of Block/Road- Sakra / Sugawalpur / Gannipur / Beghasmdak
ME Dairy to Maehhahi Muslim tola Demma
Sabha Maricha Road tal.

A For Road

- 1 Damage Location/Chainage Multiple Location damaged (0-2.58km)
2 Damage Length 0.300km
3 Nature of Damage - Crust shoulder, near culvert fouled
4 Details of Restoration Works-
i Material being used in Restoration Works- Bricks Bat, sand bag, Bamboo Pile
ii Equipments/Tools being used in Restoration Works- Roller, Tractor, manule
iii Procedure Taken up in Restoration Works- Immediate restoration of road
way, traffic opening
iv Restored Length 0.300km

B. For Bridge

- 1 Damage Location/Chainage
2 Damage Length
3 Nature of Damage
4 Details of Restoration Works-
i Material being used in Restoration Works-
ii Equipments/Tools being used in Restoration Works-
iii Procedure Taken up in Restoration Works-
iv Restored Length

Signature of JE/ AE/ EE

Signature
(Name of Inspector)

प्रतिवेदन

कार्य का नाम- सुजावलपुर गन्नीपुर बेड़ा सड़क में डेयरी से मच्छी मुरिक्मथेला
दोनवाँ सीमान तक पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में
यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- सकरा

वित्तीय वर्ष - 2020-21

प्राक्कलित राशि - Rs. 5,96,500/- (पाँच लाख छान्ने हजार पाँच सौ ०० मात्र)

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 5,96,500/- है, का 50 मुजफ्फरपुर
प्रखण्ड- सकरा में यातायात बहाली हेतु आपातकालिन मरम्मत के
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा
दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में डेयरी मुजफ्फरपुर से मच्छी मुरिक्मथेला तक
करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चालू अनुसूचित दर पर तैयार किया गया है। इसकी
घटनोत्तर स्वीकृति अपेक्षित है।

01/12/20
कनीय अभियंता

01/12
सहायक अभियंता,

01/12/20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुज०
पूर्वी-1

NAME OF WORK:- Restoration work of Road from Sujawalpur Gannipur Bejha Sandak me Dairy to Machhahi muslim tola Donma siman Sabha Maricha Road tak

Total Length :- 2.58km

Restoration Length :- 0.3km

ABSTRACT OF COST

Sl. No.		Unit	Rates	Quantity	Amount
1	Providing and Laying of Brick Bats: Placing tractor at loading point loading with front end loader dumpoing, turning for return trip exluding time for haulage and return trip	Cum	1,768.60	201.64	356,621.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in .size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	522.50	25,812.00
3	Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	3,400.00	123,080.00
	Total Amount			Rs.	505,513.00
	Add for GST @ 12%			Rs.	60,662.00
	Add for Labour Cess @ 1%			Rs.	5,055.00
	Add for Seigniorage Fee			Rs.	25,232.00
	Gross Total Amount			Rs.	596,462.00
	Say			Rs.	596,500.00

[Signature]
J.E. 01.12.20

[Signature]
A.E. 01/12
RWD, Sub-Division, Sakra

[Signature]
Executive Engineer
RWD(W) Div.Muzaffarpur East 1

Technically approved for Rs. 596500/-
(Rupees five lac Ninety six thousand five hundred) only.

[Signature]
S.E., RWD (W)
MUZAFFARPUR CIRCLE
27/12/20