

MBNo - 2583



GOVERNMENT OF BIHAR

NAME OF WORK :- Bariyarpur Kandh bhuneshwar ray ke ghar
se harijan tola noon nadi tak

(FDR PART-A)

Restoration Length :- 0.295 km

Block:- Sakra

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 5,89,600.00

**-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST 1**

प्रतिवेदन

कार्य का नाम:-

कल्याणदास गांधी ग्रामोत्तर राय के वर के वरिष्ठ
दलानुयोजक पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में
यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड:-

2020-21

वित्तीय वर्ष -

2020-21

प्राक्कलित राशि - Rs.

589600:-

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 589600:- है,

प्रखण्ड-2020-21 में यातायात बहाली हेतु आपातकालीन मरम्मत के
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा
दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ को चालू
करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी
घटनोत्तर स्वीकृति अपेक्षित है।

12/12/20

कनीय अभियंता

12/12/20

सहायक अभियंता

12.12.20

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुजफ्फर
पूर्व-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- M42 Farpur East-1
2 Name of Block/Road- Sakra/Baziyarpur Kandi Bhuneshwar
Thakur Naykaghar Hazijanola Moonnadi
Tall

A For Road

- 1 Damage Location/Chainage Multiple Location damaged (0-1.435km)
2 Damage Length 0.295 km
3 Nature of Damage Near culvert & shoulder & Embankment
4 Details of Restoration Works-

- i Material being used in Restoration Works- Brick bats Sand bag, bamboo pile
ii Equipments/Tools being used in Restoration Works- Roller
iii Procedure Taken up in Restoration Works- Immediate restoration of traffic opening
iv Restored Length - 0.295 km

B. For Bridge

- 1 Damage Location/Chainage
2 Damage Length
3 Nature of Damage
4 Details of Restoration Works-
i Material being used in Restoration Works-
ii Equipments/Tools being used in Restoration Works-
iii Procedure Taken up in Restoration Works-
iv Restored Length

Signature of JE/ AE/ EE

Signature
(Name of Inspector)

NAME OF WORK:- Bariyarpur Kandh bhuneshwar ray ke ghar se harijan tola noon nadi tak

Total Length :- 1.435 km

Restoration Length :- 0.295 km

ABSTRACT OF COST

Sl. No.		Unit	Rates	Quantity	Amount
1	Providing and Laying of Brick Bats: Placing tractor at loading point loading with front end loader dump, turning for return trip excluding time for haulage and return trip	Cum	1,768.60	232.18	4,10,634.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	932.50	46,066.00
3	providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification and direction of E/I	Rm	26.40	150.00	3,960.00
4	Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	1,029.00	37,250.00
	Total Amount			Rs.	4,97,910.00
	Add for GST @ 12%			Rs.	59,749.00
	Add for Labour Cess @ 1%			Rs.	4,979.00
	Add for Seigniorage Fee			Rs.	26,926.00
	Gross Total Amount			Rs.	5,89,564.00
	Say			Rs.	5,89,600.00

J.E.

A.E.
RWD, Sub-Division, Sakra

Executive Engineer
RWD(W) Div. Muzaffarpur East 1

Technically approved for Rs. 5,89,600.00
(Rupees five Lac Eighty Nine thousand Six hundred) only

S.E., RWD(W)

MUZAFFARPUR CIRCLE

27/11/20