

Inspection Report for Flood Damage Work

Date


1. Name of PIUs- Muzaffarpur East-1
2. Name of Block/Road- Sakri / Machhiti to Mehsi


A For Road

1. Damage Location/Chainage multiple Location damaged (0-4.45km)
2. Damage Length 0.365km
3. Nature of Damage Near Culvert, & shoulder & crust
4. Details of Restoration Works-
 - i. Material being used in Restoration Works- Bricks Bat, NP3 Pipe
 - ii. Equipments/Tools being used in Restoration Works- Immediate Roller, Tractor, JCB
 - iii. Procedure Taken up in Restoration Works- Immediate Rerestoration of traffic opening
 - iv. Restored Length 0.365km

B. For Bridge

1. Damage Location/Chainage
2. Damage Length
3. Nature of Damage
4. Details of Restoration Works-
 - i. Material being used in Restoration Works-
 - ii. Equipments/Tools being used in Restoration Works-
 - iii. Procedure Taken up in Restoration Works-
 - iv. Restored Length


Signature of JE/ AE/ EE


Signature
(Name of Inspector)

प्रतिवेदन

कार्य का नाम:-

गहरी से गहरी

.....पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- सकरा

वित्तीय वर्ष - 2020-21

प्राक्कलित राशि - Rs. - 11,99,400/00 एक लाख नब्बाने हजार चार सौ (00)

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 11,99,400/00 है, मुजफ्फरपुर पूर्व-1 प्रखण्ड- सकरा में यातायात बहाली हेतु आपातकालिन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521, दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में आवृत्ति 2521, भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।

01.12.20
कनीय अभियंता

Jan
सहायक अभियंता

4.12.20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुज0
पूर्व-1

ME OF WORK:-

Restoration work of Road Machahi to mehsi

Total Length :- 4.45 Km

Restoration Length :- 0.365 km

ABSTRACT OF COST

	Unit	Rates	Quantity	Amount
Providing and Laying of Brick Bats:	Cum	1,768.60	544.36	962,755.00
Placing tractor at loading point loading with front end loader umpong, turning for return trip exluding time for haulage and return time				
Providing and laying reinforced cement concrete pipe NP3 1000 mm dia for culvert on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection work backfilling concrete and	m	3,312.20	15.00	49,683.00
Total Amount			Rs.	1,012,438.00
Add for GST @ 12%			Rs.	121,493.00
Add for Labour Cess @ 1%			Rs.	10,124.00
Add for Seigniorage Fee			Rs.	55,361.00
Gross Total Amount			Rs.	1,199,416.00
Say			Rs.	1,199,400.00

[Signature]
01/12/20
J.E.

[Signature]
01/12
A.E.
RWD, Sub-Division, Sakra

[Signature]
4.12.20
Executive Engineer
RWD(W) Div. Muzaffarpur East 1

Technically approved for Rs. 1,199,400/-
(Rupees Eleven Lac Ninety Nine Thousand four hundred) only.

[Signature]
23/12/20
S.E., RWD(W)

MUZAFFARPUR CIRCLE
[Signature]
23/12/20