

Inspection Report for Flood Damage Work

Date:


1. Name of PIUs RWD works Division Gupallganj-2
2. Name of Block/Road Sidhiwalia / Vishunpur to Gangwa

A. For Road

1. Damage Location/Chainage : 100 to 300 M | 600 to 700 M | 1450 to 1700 M
2. Damage Length : 150 M | 30 M | 155 M
3. Nature of Damage : Road partially damage water overtoped on road
4. Details of Restoration Works :
 - i. Material being used in Restoration works : Brick bats, Rubish
 - ii. Equipments/Tools being used in Restoration works : JCB, Tractor with Trol
 - iii. Procedure taken up in Restoration works :
 - iv. Restored Length : 355 M

B. For Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage : NA
4. Details of Restoration Works :
 - i. Material being used in Restoration works :
 - ii. Equipments/Tools being used in Restoration works : NA
 - iii. Procedure taken up in Restoration works :
 - iv. Restored Length :


JE


AE


EE


Signature

(Name of Inspector)



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

FLOOD DAMAGED REPAIR (F.D.R)

STATE :- BIHAR
DISTRICT :- GOPALGANJ
BLOCK :- SIDHWALIA

Vishunpur to Gangawa

ESTIMATED COST RS 519500.00

SUBMITTED BY:
EXECUTIVE ENGINEER
RWD (W) DIVISION -
GOPALGANJ - 2

Report.

Name of work :- Vishunpur to Gangawa

Estimated Cost :- Rs 519500.00

Total length of road :- 3.03 km.

Description :- The present estimate has been framed under the supervision of Assistant engineer in accordance with the order of Executive Engineer , RWD , WD Gopalganj-2 , letter no – 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transportation has been obstructed . The immediate motorable work is necessary in public interest . Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats .

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.


18-09-20
J.E.


18/9/20
A.E.


18/9/20
E.E.

Detailed Estimate For Motorable Work in road from Vishunpur to Gangawa damaged due to Heavy rain / Flood for Year . 2020-2021

Sr.	Items	no.	L (M.)	W M.)	D (M.)	Qty.	unit	rate	Amount
1	Providing brick bats billed in ditches including all cost of Labour & Material with all complete job .								
	CH- 100 M to 300 M	1	150.00	3.50	0.15	78.75	M ³		
	CH- 600 M to 700 M	1	10.00	3.75	0.15	5.63	M ³		
		1	20.00	3.75	0.15	11.25	m ³		
	CH- 1400 M to 1700 M	1	155.00	3.75	0.20	116.25	M ³	2492.11	5110.78
						211.88		2427.65	514358.34
	Add 1% contingency							5111.20	5143.58
								Total	516189.20
									519501.92
								Say	519500.00

Say Rs. 5.162 Lacs

[Signature]
18-09-20
JE

[Signature]
18/09/20
AE

[Signature]
18/9/20
EE

Technically Approved for Rs 5.162 lac (Rupees Five Lacs Sixteen Thousand & Two Hundred) only

[Signature]
13/01/21
Superintending Engineer
RWD Work, Circle-Siwan
[Signature]
11/01/2021