

Inspection Report for Flood Damage Work

Date:


1. Name of PIUs RWD, works Division, Gopalganj-2
2. Name of Block/Road- Sidhwaalia / Sidhwaalia Baddiha PWD road to Dervuli road via Ahir tola, Purni
Harjan tola Ujjaintola, Rajpurthi

A. For Road

1. Damage Location/Chainage : 300m | 600m
2. Damage Length : 15.0m | 30.0m
3. Nature of Damage : Road washout
4. Details of Restoration Works :
 - i. Material being used in Restoration works : Brick bats
 - ii. Equipments/Tools being used in Restoration works: JCB, Tractor with Trolley
 - iii. Procedure taken up in Restoration works :
 - iv. Restored Length : 45.0m


B. For Bridge

1. Damage Location/Chainage : |
2. Damage Length : | NA
3. Nature of Damage : |
4. Details of Restoration Works :
 - i. Material being used in Restoration works : |
 - ii. Equipments/Tools being used in Restoration works: | NA
 - iii. Procedure taken up in Restoration works : |
 - iv. Restored Length : |


JE


AE


EE 18/9/20

Signature 
(Name of Inspector)



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

FLOOD DAMAGED REPAIR (F.D.R)

STATE :- BIHAR
DISTRICT :- GOPALGANJ
BLOCK :- SIDHWALIA

Sidhwalia Baldih PWD Road To Devkuli Road Via Ahir Tola, Purvi Harijan Tola,
Ujjain Tola, Rajput Tola

ESTIMATED COST RS 1655050.00-
1471150.00

SUBMITTED BY:
EXECUTIVE ENGINEER
RWD (W) DIVISION -
GOPALGANJ - 2

Report.

Name of work :- Sidhwalia Baldih PWD Road To Devkuli
Road Via Ahir Tola, Purvi Harijan Tola,
Ujjain Tola, Rajput Tola

Estimated Cost :- ~~1655050.00~~ 1471150.00

Total length of road :- 2.014 KM


Description :- The present estimate has been framed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter no - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transportation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of road. This provision has a purpose to put a check on the erosion of embankment of road.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.


18-09-20
J.E.


18/09/20
A.E.


18/9/20
E.E.

Detailed Estimate For Motorable Work in road from Sidhwalia Baldih PWD Road To Devkuli Road Via Ahir Tola, Purvi Harijan Tola, Ujjain Tola, Rajput Tola damaged due to Heavy rain / Flood for Year . 2020-2021

Sr.	Items	no.	L (M.)	W M.)	D (M.)	Qty.	unit	rate	Amount
1	Providing brick bats billed in ditches including all cost of Labour & Material with all complete job .								
	CH- 300 M					90.00			
	Ditch	1	10.00	5.00	1.80	135.00	M ³		
	Embankment	1	10.00	4.00	1.50	90.00	M ³		
	CH- 600 M					60.00			
	Ditch	1	30.00	5.00	1.80	270.00	M ³		14472.66
	Embankment	1	30.00	4.00	1.50	180.00	M ³	2412.11	1456590.00
						600.00	M ³	2427.65	4638663.75
	Add 1% contingency							14473	16386.6+14566
							Total		1655050.39
							Say		1655050.00

Rs 14,61,739.20

Say Rs 14,61,739.20
Say Rs 14.617 Lacs

[Signature]
18-09-20
JE

[Signature]
18/9/20
AE

[Signature]
18/9/20
EE

Technically Approved for Rs 14.617 Lacs (Rupees fourteen Lacs.
Sixty one Thousand & Seven Hundred) only

[Signature]
13/01/21
Superintending Engineer
RWD Work Circle-Siwan

[Signature]
11/01/2021