

Inspection Report for Flood damage work
K. E. R. W. D. Division, Marhauza

Date:

1. Name of PIUs-

2. Name of Block/Road- Maerak. Estimate for repair at Road Blockade
(Damage by Flood) for Motorable work in Maerak Lakhepur
A. For Road Road chain for Baluwika Kumbhupura Baladempur Chhapriya Saphi
parts

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

187.60 m

Cut in Road; Quite Flood & ruin

: B&B Bets

- Tractor, Roller, 2 TON

: - B&B Bets

: - 187.60 m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AE/EE

21/11/20
AE

21/11/2020
Signature

(Name of Inspector)



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

FDR

**PLAN HEAD FDR (2245)
(2020-2021)**



**ESTIMATE FOR REPAIR OF ROAD BREACHES (DAMAGE BY FLOOD) FOR
MOTARABLE WORK IN MASHRAKH LAKHANPUR ROAD CHAINPUR TO
BALUA VIA KAWALPURA BAHADURPUR CHHAPIA SAPAHI PATH**

DISTRICT	:-	Saran	
DIVISION	:-	Marhaura	
BLOCK	:-	Mashrakh	
TOTAL LENGTH OF ROAD	:-	7.000	KM
TOTAL COST OF CONSTRUCTION	:-	39.381	Lac
TOTAL COST OF PROJECT	:-	39.381	Lac

FDR(2020-2021)

प्रतिवेदन

पथ का नाम:- Mashrakh Lakhanpur Road Chainpur To Balua Via
Kawalpura Bahadurpur Chhapia Sapahi Path
पथ की लम्बाई:- 7.000 KM.
प्राक्कलित राशि:- 3938115 रु
प्रखंड:-मशरख
जिला:-सारण

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमंडल मढ़ौरा के प्रखंड अंतर्गत बाढ़ से क्षतिग्रस्त पथों के मोटरेबुल कार्य प्राक्कलन कार्यपालक अभियंता, ग्रामीण कार्य विभाग कार्य प्रमंडल मढ़ौरा के निर्देशानुसार तैयार किया गया है।

विदित है कि माह जुलाई एवं अगस्त

2020 में गंडक नदी के बांध के टूटने एवं अतिवृष्टि के कारण आयी बाढ़ के कारण निर्मित/निर्माणाधीन पथों में काफी क्षति हुई है। पानी के तेज बहाव के कारण पथों में हुई कटाव से आवागमन प्रभावित हुआ है साथ ही दिनांक 3.11.2020 को बिहार विधान सभा का चुनाव निर्धारित है। बूथों तक वाहन का आवागमन आवश्यक है जिस कारण से चुनाव कार्य एवं लोगों की कठिनाईयों को देखते हुए तथा उच्चाधिकारी के निर्देशानुसार पथों को तत्काल मोटरेबुल करने का निर्देश दिया गया है ताकि सभी बूथों पर वाहन का आवागमन सुनिश्चित हो सके।

उपरोक्त आलोक में क्षतिग्रस्त पथों में तत्काल Brick Bats से भरकर वाहन का आवागमन चालू किया गया है।

प्राक्कलन वर्तमान अनुसूचित दर पर तैयार कर आवश्यक कारवाई हेतु समर्पित किया जाता है।


4.12.20
कनीय अभियंता


04/12/20
सहायक अभियंता


कार्यपालक अभियंता

FDR

GENERAL ABSTRACT OF COST


Block:- Mashrakh

District:- Saran

Length of Road:-- 7.000 KM

Name of Road:-- Estimate for Repair of Road Breaches (Damage By Flood) For Motarable Work in Mashrakh Lakhanpur Road Chainpur To Balua Via Kawalpura Bahadurpur Chhapia Sapahi Path

SL. No.	Item of Work	Amount
A	TOTAL COST	: 39.381 Lacs
	TOTAL	: 39.381 Lacs


4.12.20
Junior Engineer


04/12/2020
Asstt. Engineer


Executive Engineer

Technically approved for Rs 39.38100/- (Thirty nine lakh thirty eight thousand one hundred) 4-12-20

SE
अधीक्षक अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, छपरा

ANNEXTURE-1

Estimate for Repair of Road Breaches (Damage By Flood) For Name Of Road :- Motarable Work in Mashrakh Lakhanpur Road Chainpur To Balua Via Kawalpura Bahadurpur Chhapiap Saphi Path							Block:- Mashrakh
Sl. No.	Description	Nos.	LENGTH (m)	WIDTH (m)	HEIGHT (m)	UNIT	QUANTITY
1	CH-3.30 Km Flank(L/S)	1	9.00	1.00	0.90	CUM	8.10 m3
2	CH-3.30 Km Flank(R/S)	1	9.00	1.00	0.90	CUM	8.10 m3
	CH-3.30 Km	1	21.00	6.00	3.50	CUM	441.00 m3
3	CH-3.50 Km Flank(L/S)	1	12.00	1.00	0.90	CUM	10.80 m3
4	CH-3.50 Km Flank(R/S)	1	12.00	1.00	0.90	CUM	10.80 m3
5	CH-3.50 Km	1	16.00	6.00	2.90	CUM	278.40 m3
6	CH-3.50 Km	1	9.00	6.00	0.60	CUM	32.40 m3
7	CH-3.50 Km	1	10.00	1.10	0.70	CUM	7.70 m3
8	CH-4.750 Km	1	6.00	6.00	1.52	CUM	54.72 m3
9	CH-4.750 Km FLANK L/S	1	10.00	1.10	1.00	CUM	11.00 m3
10	CH-4.900 Km	1	9.80	6.00	2.90	CUM	170.52 m3
11	CH-5.000 Km	1	13.00	6.00	3.10	CUM	241.80 m3
12	CH-5.000 Km FLANK R/S	1	20.00	1.00	1.10	CUM	22.00 m3
13	CH-5.950 Km	1	2.00	6.00	0.60	CUM	7.20 m3

Estimate for Repair of Road Breaches (Damage By Flood) For
Name Of Road :- Motarable Work in Mashrakh Lakhampur Road Chainpur To
Balua Via Kawalpura Bahadurpur Chhapia Sapahi Path

Block:- Mashrakh

Sl. No.	Description	Nos.	LENGTH (m)	WIDTH (m)	HEIGHT (m)	UNIT	QUANTITY
14	CH-6.000 Km	1	22.40	6.00	3.10	CUM	416.64 m3
15	CH-6.100 Km	1	6.40	6.00	2.80	CUM	107.52 m3
TOTAL QUANTITY =							1828.70 m3


4.12.20

JE
RWD


04/12/2020

AE
RWD


11/12/20

EE
RWD