

Inspection Report for Flood Damage Work

Date:

1. Name of PIUs RWD, works Division, Gopalganj-2
2. Name of Block/Road - Sidhiwala / Banjariya Dhala to Banjariya Gao

A. For Road

1. Damage Location/Chainage : 0 to 300m | 300 to 500m |
2. Damage Length : 85m | 39m |
3. Nature of Damage : Road w/out & over topped water
4. Details of Restoration Works :
 - i. Material being used in Restoration works : Brick bats / Samal
 - ii. Equipments/Tools being used in Restoration works : JCB, Tractor with Trolley
 - iii. Procedure taken up in Restoration works :
 - iv. Restored Length : 124 M / 500m

B. For Bridge

1. Damage Location/Chainage : |
2. Damage Length : |
3. Nature of Damage : | NA
4. Details of Restoration Works :
 - i. Material being used in Restoration works :
 - ii. Equipments/Tools being used in Restoration works : | NA
 - iii. Procedure taken up in Restoration works :
 - iv. Restored Length



JE



AE



EE

Signature

(Name of Inspector)



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

FLOOD DAMAGED REPAIR (F.D.R)

STATE :- BIHAR
DISTRICT :- GOPALGANJ
BLOCK :- SIDHWALIA

Banjariya Dhala to Banjariya Gao

ESTIMATED COST RS 605850.00

SUBMITTED BY:
EXECUTIVE ENGINEER
RWD (W) DIVISION
GOPALGANJ - 2

Report.

Name of work :- Banjariya Dhala to Banjariya Gao

Estimated Cost :- Rs 605850.00

Total length of road :- 1.215 KM

Description :- The present estimate has been framed under the supervision of Assistant engineer in accordance with the order of Executive Engineer , RWD , WD Gopalganj-2 , letter no - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transportation has been obstructed . The immediate motorable work is necessary in public interest . Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats . There has also been a provision of filling sands over brickbats and old bricks soling.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.


18-09-20
J.E.


18/09/20
A.E.


18/9/20
E.E.

Detailed Estimate For Motorable Work in road from Banjariya Dhala to Banjariya Gao damaged due to Heavy rain / Flood for Year . 2020-2021

Sr.	Items	no.	L (M.)	W M.)	D (M.)	Qty.	unit	rate	Amount
1	Providing brick bats billed in ditches including all cost of Labour & Material with all complete job .								
	CH- 0 M to 300 M	1	30.00	3.05	0.15	13.73	M ³		
		1	15.00	3.05	0.15	6.86	M ³		
		1	7.00	3.05	0.15	3.20	M ³		
		4	3.00	3.05	0.15	5.49	M ³		
		1	21.00	3.05	1.00	64.05	M ³		
	CH - 300 M to CH - 500 M	1	24.00	3.05	1.00	73.20	M ³		
		1	10.00	3.05	0.15	4.58	M ³		
		1	5.00	3.00	1.50	22.50	M ³	2412.11	467009.20
						193.61	M ³	2427.65	470,005.18
								865.74	67995.20
	Providing Local Sand filling complete job	1	500.00	3.00	0.10	150.00	M ³	5349.14	599866.18
								5349.20	5998.66
	Add 1% contingency							Total	605864.84
								Say	605850.00

Rs. 540263.20

Say Rs. 5.403 Lacs

[Signature]
18-09-20
JE

[Signature]
18/09/20
AE

[Signature]
18/9/20
EE

Technically Appraised for Rs 5.403 Lacs (Rupees Five Lacs forty Thousand & Three Hundred only)

[Signature]
13/01/21
Superintending Engineer
RWD Work. Circle-Siwan
11/01/21