

Inspection Report For Flood Damage Work

Date :

1 Name of PIUs : Gopalgarh-2

2 Name of Block/Road : Sailkuthpur / Hamidpur To Kaitpur

A For Road

1 Damage Location / Chainage : 300m to 330m, 640m to 675m, 1510m to 1525m

2 Damage Length : 276m 1550m to 1600m, 1610m to 1630m, 1650m to 1675m
1970m to 2015m, 2340m to 2386m

3 Nature of Damage : Heavy Rain / Flood

4 Details of Restoration Works:

i. Material being used in Restoration Works: Brick Bets

ii Equipments / Tools being used in Restoration Works: JCB, Tractor, Trolly, Belch, Shovel

iii Procedure taken up in Restoration Works: Yes

iv Restored Length: 276m

B For Bridge

N/A

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

4 Details of Restoration Works:

i. Material being used in Restoration Works :

ii Equipments / Tools being used in Restoration Works :

iii Procedure taken up in Restoration Works:

iv Restored Length :

PRP
25/9/2020
JE

25.09.2020
AE

25/9/20
EE

28/12/2020
Signature
(Name of Inspector)



ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR
DISTRICT :- GOPALGANJ
BLOCK :- BAIKUNTHPUR

Hamidpur To Kritpura

ESTIMATED COST - RS.

~~6982000.00~~ Rs 67,07,000 = 00

SUBMITTED BY :-
EXECUTIVE ENGINEER
RWD (W) DIVISION
GOPALGANJ-2

Report

Name of Work :- Motorable work of Hamidpur To Kritpura

Estimated Cost :- ~~6982000.00~~ Rs 6707 000 000


Total length of Road :- 3.060 km


Description :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road. Hence there has been a provision of laying 3 Nos of R.C.C. NP3 1000 MM Dia hume pipe.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.


19/09/2020
J.E.


19.09.2020
A.E.


19/9/20
E.E.

**Detailed Estimate For Motorable Work in Road from Hamidpur To Kritpura
damaged due to Heavy rain/flood for year 2020-2021**

Items	No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amount
Providing brick bats billed in ditches including all cost of labour & material with all complete job.								
CH - 300 M to 330 M	1	30.00	4.70 5.20	3.50	512.50 546.00	M3		
CH - 640 M to 675 M	1	30.00	3.50	5.20	546.00	M3		
	1	5.00	3.00	2.00	30.00	M3		
CH - 1510 M to 1525 M	1	15.00	3.00	4.00	180.00	M3		
CH - 1550 M to 1600 M	2	25.00	2.50	3.50	437.50	M3		
CH - 1610 M to 1630 M	1	30.00	5.00	4.00	600.00			
CH - 1650 M to 1675 M	1	21.00 25.00	2.25 3.00	2.00	94.50 150.00	M3		
CH - 1970 M to 2015 M	1	30.00	1.20	3.20	115.20	M3		
	1	15.00	1.60	2.10	50.40	M3		
CH - 2340 M to 2386 M	1	30.00	2.50	1.50	112.50	M3		
	1	14.00 16.00	1.60 2.00	1.30	29.12 41.60	M3		
Less for H.P.	0	1.23	1.23	0.95	0.00	M3		
					-2809.20		2412.11	653614324
					2707.72		-2427.65	6819754.38
Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	9 6	2.50			22.50 15.00	M	2733.35 4159.56	6578251.76 41003.20 93590.10 62393.40 6690645.16
							6577140	6913344.48
Add 1 % Contingency							657712	66406.45
					6642917			69133.44
							Total	6707000.00
							Say	6982477.92
								6982000.00

Rs 6707000.00
6642917.20
Say Rs 66.429 L

[Signature]
19/9/2020

J.E.

[Signature]
19.09.2020

A.E.

[Signature]
19/9/20

E.E.

Technically Approved for Rs 66.429 L (Rupees Sixty Six Lacs Forty Two Thousand & Nine Hundred) only

Superintending Engineer
R.W.D. Work Circle-Sivan

[Signature]
13/01/21