

Inspection Report For Flood Damage Work

Date :

1 Name of PIUs: Gobalgani - 2.2 Name of Block/Road: Balkunthpur / Rajapatti PWD Path To Pradhan Mantri Road.**A For Road**1 Damage Location / Chainage: 30m to 40m, 40m to 45m, 200m to 209m, 600m to 665m, 1000m to 1007m, 1200m to 1207, 1300m to 1305m2 Damage Length: 180m 1350m to 1354m, 1400m to 1412m, 1500m to 1525m, 1600m to 1629m3 Nature of Damage: Heavy Rain / Flood

4 Details of Restoration Works:

i. Material being used in Restoration Works: Brick Batsii Equipments / Tools being used in Restoration Works: Tractor, JCB, Puli, Belcher, shoveliii Procedure taken up in Restoration Works: Yesiv Restored Length: 180m**B For Bridge**N/A

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

4 Details of Restoration Works:

i. Material being used in Restoration Works :

ii Equipments / Tools being used in Restoration Works :

iii Procedure taken up in Restoration Works:

iv Restored Length :

Prasad
25/9/20
JE

Prasad
25.09.2020
AE

Prasad
25/9/20
EE

Prasad
16/12/20
Signature
(Name of Inspector)



ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR
DISTRICT :- GOPALGANJ
BLOCK :- BAIKUNTHPUR

Rajapatti PWD Path To Pradhan Mantri Road

ESTIMATED COST - RS.

~~5022600.00~~ Rs 4732700.00

**SUBMITTED BY :-
EXECUTIVE ENGINEER
RWD (W) DIVISION
GOPALGANJ-2**

Report

Name of Work :- Motorable work of Rajapatti PWD Path To Pradhan Mantri Road

Estimated Cost :- ~~5022600.00~~ 4732700.00


Total length of Road :- 2.200 km


Description :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road. Hence there has been a provision of laying 2 Nos of R.C.C. NP3 1000MM Dia hume pipe.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.


19/9/2020
J.E.


19.09.2020
A.E.


19/9/20
E.E.

iled Estimate For Motorable Work in Road from Rajapatti PWD Path To Pradhan Mantri Road damaged due to Heavy rain/flood for year 2020-2021

Items	No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amount
Providing brick bats billed in ditches including all cost of labour & material with all complete job.								
CH - 30 M to 42 M	1	12.00	6.00	6.00	432.00	M3		
CH - 40 M to 45 M	1	5.00	3.00	1.50	22.50	M3		
CH - 200 M to 209 M	1	9.00	2.10	3.00	56.70	M3		
CH - 600 M to 665 M	2	30.00	2.60	6.00	936.00	M3		
	1	5.00	2.40	5.30	63.60	M3		
CH - 1000 M to 1007 M	1	7.00	1.40	1.45	14.21	M3		
CH - 1200 M to 1207 M	1	7.00	0.90	1.20	7.56	M3		
CH - 1300 M to 1305 M	1	5.00	1.35	1.50	10.13	M3		
CH - 1350 M to 1354 M	1	4.00	3.10	2.50	31.00	M3		
CH - 1400 M to 1412 M	1	12.00	4.50	2.00	108.00	M3		
CH - 1500 M to 1525 M	1	25.00	4.10	1.70	174.25	M3		
CH - 1600 M to 1629 M	1	29.00	3.50	1.75	177.63	M3		
Less for H.P.	1.58	1.23	1.23	0.95	2.27	M3	2412.11	46145352
					2031.30		2427.65	4931283.35
2 Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	4	2.50			10.00	M	2733.59	4644270.43
							4159.56	27335
								41595.60
								464187124
								4685870105
								4972878.95
Add 1 % Contingency							464192	46858.70
								49728.79
								473278.75
							Total	5022607.74
							Say	5022600.00

Rs 4732700.00

Rs 4688290 =

Say Rs 46.8836

[Signature]
19/9/2020
J.E.

[Signature]
19.09.2020
A.E.

[Signature]
19/9/20
E.E.

Technically Approved for Rs 46.8836 (Rupees Forty six lac Eighty Eight Thousand & Three Hundred) only

[Signature]
19/10/21
Superintending Engineer
RWD Work Circle-Siwan
11/9/2021