



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

FDR

PLAN HEAD FDR(2245) (2020-2021)



MOTORABLE OF ROAD FROM NH-19 TELEPHONE EXCHANGE TO GULARIYA GHAT

DISTRICT	:-	Saran	
DIVISION	:-	Sonpur	
BLOCK	:-	Sonpur	
TOTAL LENGTH OF ROAD	:-	1.900	KM
TOTAL COST OF CONSTRUCTION	:-	5.181	Lac
TOTAL COST OF PROJECT	:-	5.181	Lac


FDR(2020-2021)

प्रतिवेदन


प्रमंडल का नाम :- ग्रामीण कार्य विभाग कार्य प्रमंडल सोनपुर
पथ का नाम :- NH-19 टेलीफोन एक्सचेंज से गुलरिया घाट
पथ की लम्बाई :- 1.900 Km.
प्राक्कलित राशि :- 518053 रु
प्रखंड :- सोनपुर
जिला :- सारण

प्रस्तुत प्राक्कलन सारण जिला अंतर्गत NH-19 टेलीफोन एक्सचेंज से गुलरिया घाट तक पथ बाढ़ से क्षतिग्रस्त (F.D.R.) पथांश का यातायात पुर्नस्थापन (Motorable) कार्य तैयार किया गया है। इस वर्ष अचानक अत्यधिक बाढ़ आने के कारण पथ के CH-400 m से 1200 m तक में जगह-जगह क्षतिग्रस्त होने के कारण आवागमन बाधित हो गया, तत्काल पथ मरम्मत हेतु पथांश में Brick Bats भरकर कटाव से बचाव का कार्य करते हुए यातायात को पुर्नस्थापित किया गया है।

पथ मरम्मत कार्य का प्राक्कलन वर्तमान अनुसूची दर पर ही तैयार किया गया है प्राक्कलन की स्वीकृति अपेक्षित है।


कनीय अभियंता

सहायक अभियंता


कार्यपालक अभियंता

FDR

GENERAL ABSTRACT OF COST


Block:- Sonpur

District:- Saran


Length of Road:- 1.900 KM

Name of Road:- Motorable of Road From NH-19 Telephone Exchange To Gulariya Ghat

SL. No.	Item of Work	Amount
A	TOTAL COST	: 5.181 Lacs
	TOTAL	: 5.181 Lacs



Junior Engineer

Asstt. Engineer


Executive Engineer

T/A Approved Rs. 5.181 Lakh (Rupees Five Lakh Eighteen Thousand one hundred only)

SE
RWD


S.E. RWD
Chopra

Name Of Road :-		Motorable of Road From NH-19 Telephone Exchange To Gulariya Ghat						Block :-	Sonpur	DISTRICT:-	Saran	LENGTH :-	1.900 KM.
Sl No.	SDB SL.NO	MORD Ref.No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)		
1	8.1.3.2 (iii)		BRICK BATS										
			Providing brick bats including spreading laying,Labour for dry graded jhama khoa folter under Brick Pitching or boulder pitching in slope or apron including light ramming etc. All complete job as per approved design specification and direction of E/L including carriage cost of bricks.										
			CH-200 To 600 M	Cum	4.00	2.50	1.500	0.50	7.50				
				Cum	4.00	1.50	1.500	0.40	3.60				
				Cum	1.00	3.00	2.500	1.50	11.25				
				Cum	1.00	3.00	6.200	1.50	27.90				
				Cum	1.00	3.75	1.500	0.50	2.81				
				Cum	1.00	100.00	3.750	0.50	187.50				
									240.56	2,153.51	5,18,053.00		
									TOTAL COST IN RS.=				5,18,053.00

Inspection Report for flood damage work

Date :

1. Name of PIUs : AKKALISH KUMAR

2. Name of Block/Road : SONPUR — NH-19

(A) For Road - NH-19 Telephone exchange to Gulariya ghat.

1. Damage Location/Chainage : CH - 400 - 1200 A.O

2. Damage Length : 0.800 K.M

3. Nature of Damage : Road cutting and surface Damage

4. Details of Restoration :

(i) Material being used in Restoration : BRICK BAT

(ii) Equipment/Tools being used in Restoration works : tractor and Roller

(iii) Procedure taken up in Restoration works : BRICK BAT FILLING and compacting.

(iv) Restored Length : 0.800 K.M.

(B) For Bridge

1. Damage Location/Chainage : ✓

2. Damage Length : ✓

3. Nature of Damage : ✓

4. Details of Restoration : ✓

(i) Material being used in Restoration : ✓

(ii) Equipment/Tools being used in Restoration works : ✓

(iii) Procedure taken up in Restoration works : ✓

(iv) Restored Length : ✓

Signature of JE/AF/EE/

Signature

(Name of Inspector)