



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar



BIHAR RURAL ROADS PROJECT Bihar Rural Road Development Agency (BRRDA) Govt. of Bihar

FDR

YEAR -2020-2021

FLOOD DAMEGED REPORT



Name of the Road :-

RESTORATION OF ROAD HARDIYA BT ROAD to TO IMALIYA MORE

DISTRICT	:	SIWAN	
DIVISION	:	Maharajganj	
BLOCK	:	LAKRINABIGANJ	
TOTAL LENGTH OF ROAD	:	0.000	KM
TOTAL COST OF CONSTRUCTION	:	1.694.1332	Lac
TOTAL COST OF PROJECT	:	1.694.1332	Lac

SUBMITTED BY:-

EXECUTIVE ENGINEER

RWD (W) DIVISION Maharajganj

SIWAN

Inspection Report For Flood Damage Work

Date - 20/12/2020

1 Name of PIUs: Maharaigani

2 Name of Block/Road: Lakshminagar/Hardiya BT Road to Goraliga Cross

A For Road

1 Damage Location/Chainage: CH → 200M to 2800M

2 Damage Length: - 35mtr

3 Nature of Damage: Heavy Flood / Rainfall

4 Details of Restoration Work:

i Material being used in Restoration Work: - Brick bats, E/W

ii Equipments /Tools being used in restoration Work: - JCB, Tractor, trolley, shovel, Hammer

iii Procedure taken up in Restoration Work:

iv Restored Length: - 35mtr

B For Bridge

1 Damage Location/Chainage:

2 Damage Length

3 Nature of Damage:

4 Details of Restoration Work:

i Material being used in Restoration Work:


ii Equipments /Tools being used in restoration Work:

iii Procedure taken up in Restoration Work:


iv Restored Length:

N/A


JE


20/12/20
AE


20/12
EE


27/12/20
Signature

E.E Gopalganj-2
(Name of Inspector)

NABARD

YEAR -2020-2021

GENERAL ABSTRACT OF COST

Block:-- LAKRINABIGANI

District:- SIWAN

Length of Road:-- 0.000 KM

Name of Road:-- RESTORATION OF ROAD HARDIYA BT ROAD to TO IMALIYA MORE

SL. No.	Item of Work	Amount
A	CONSTRUCTION COST	1.694 1.178-Lacs
	Add GST @ 12%	0.141-Lacs
	Add Labour Cess @ 1%	0.012-Lacs
	TOTAL CONSTRUCTION COST INCLUDING GST AND L.C	1.694 1.332-Lacs
	TOTAL	1.694 1.332-Lacs

Junior Engineer

Asstt. Engineer

Executive Engineer

Superintending Engineer

R.W.D. Circle-Siwan

SUMMARY OF COST ESTIMATE FOR THE PROJECT

PACKAGE NO.

NAME OF ROAD :

RESTORATION OF ROAD HARDIYA BT ROAD to TO IMALIYA

DISTRICT

MORE

BLOCK

SIWAN

DIVISION

LAKRINABIGANJ

LENGTH OF ROAD (in Km)

Maharajganj

LENGTH OF BT PAVEMENT

0.000

LENGTH OF CC PAVEMENT

0

CD STRUCTURES

0

HUME PIPE

0

RCC CULVERT

0

BOX CELL CULVERT

0

CAUSEWAY / MINOR BRIDGE

0

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
2	EARTHWORK	3842.000
3	BRICK BATS	165528.114003.000
4	HP Pipe NP3	
5	EC bag	0.000
TOTAL		169370
		117845.000
ADD GST @ 12 %		14141.400
ADD LABOUR CESS @ 1 %		1178.450
TOTAL COST OF PROJECT IN LACS =		169370
		133164.850


JE
RWD


AE
RWD


EE
RWD

Sl. No.	SDH SL NO	MORD Ref No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1	3.4	301.5	SUB HEAD : PREPARATORY WORKS SITE CLEARANCE, DISMANTLING Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m, transporting to the site spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m & 100 m as per Technical Specification Clause 301.5. (Including Royalty & Labour Cess) AT shoulder								
			Total quantity of earth work	cum	2	28	1.2	0.3	20.16		
			For 1000 m lead @ 100 %						20.16	190.57	3,842.00
2		401	BRICK BATS Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.								
				cum	1	2.5	3.75	0.6	5.63		
				cum	1	10	(5+4)/2	1.4	63.00	2412.06	1,65,528.00
			Total quantity	Cum					68.63	1661.25	1,14,003.00
											117845.00

169,370.00

[Signature]
JE
RWD

[Signature]
AE
RWD

[Signature]
EE
RWD