



Name of Work:- Estimate for Repair of Road breaches (Damaged by Flood) for Motorability in Repair of diversion of L043-Adapur Thana to Nakardel (VR286) High level Bridge across Bangari river For year 2020.


Head - 2245 Length-68.84M

Sl No.	Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Earth work in Excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting Only and as per Technical Specification Clause 302.3	cum	As Per	I		Appendix	596.991	412.47 382.42	246240.19 228301.00
2		Providing & Laying dry graded Brick Bats including light ramming etc. all complete as per approved design, specification and direction of E/I.	cum	As Per	II		Appendix	118.46	2085.03	246997.87
3		Providing and laying reinforced cement concrete pipe NP3 for Cross Drainage 1000mm dia	RM	3Row x2Nos x2.50M=	15M			15.000	4032.75	60491.29
TOTAL (in Rs.)										553729.35

Say Rs 554000.00



Junior Engineer,
Rural Works Department,
Works Section, Adapur


Assistant Engineer,
Rural Works Department,
Works Sub Division, Adapur


Executive Engineer,
Rural Works Department,
Works Division, Raxaul

Post facto T.A.T.S is accorded for Rs. 5,36,000.00
(.....crore.....five.....thirty six.....thousand.....hundred.....) only.


S.E. (R.W.D.)
works Circle
Motihari


29.12.20