

Name of Work:-

Estimate for Repair of Road breaches (Damaged by Flood) for Motorability in Bahadurpur to Baisakhwa For year 2020.

Head - 2245

Length-3.250KM

SI No.	Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Earth work in Excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting Only and as per Technical Specification Clause 302.3	cum	As Per			Appendix I	0.000	412.47	0.00
2		Providing & Laying dry graded Brick Bats including light ramming etc. all complete as per approved design, specification and direction of E/I.	cum	As Per			Appendix II	634.75	2085.03	1323472.79
3		Providing and laying reinforced cement concrete pipe NP3 for Cross Drainage 1000mm dia	RM	1Row x2Nos x2.50M=			5M	25.000	4032.75	100818.82
TOTAL (in Rs.)									1424291.61	
Say Rs									1424000.00	

[Signature]
21/8/20
Junior Engineer,
Rural Works Department,
Works Section, Chhouradano

[Signature]
21/8/20
Assistant Engineer,
Rural Works Department,
Works Sub Division, Chhouradano

[Signature]
21/8/20
Executive Engineer,
Rural Works Department,
Works Division, Raxaul

Post Facto T.A./TS is accorded for Rs. 14,24,000.00
(.....crore Fourteen lacs Twenty Four
.....thousand
.....hundred) only.

[Signature]
28/12/20
S.E. (R.W.D.)
works Circle
Motihari
[Signature]
29.12.20