



GOVERNMENT OF BIHAR

NAME OF WORK

Restoration work of road from Pajhi PWD road to Jitwarpur
via Ramjithpur

(FDR PART-A)

Length 7.00km

BLOCK-DARIYAPUR

DETAILED PROJECT REPORT UNDER FDR(2245)

ESTIMATED COST

Rs. 34,70,000/-

PREPARED BY
EXECUTIVE ENGINEER
RURAL DIVISION
SINGPUR

Inspection Report for flood damage work

Date:

1. Name of PIUs-

R.W.D(W) DIV Sonpur

2. Name of Block/Road-

Daryapur, Pothi PWD road to jitwarpur via
Ramgit Pur

A. For Road

1. Damage Location/Chainage: CH 3810m-3900m, CH-5600-5630m, CH-5700m-5750m,
2. Damage Length: CH-6100m-6200m, CH-6375m-6425, CH-6880-6950m
3. Nature of Damage: 575m
4. Details of Restoration: GSB, WBM Gr II, WBM Gr III Washout
- i Material being used in Restoration: GSB, WBM Gr II, WBM Gr III
- ii Equipment/Tools being used in Restoration works: Yes
- iii Procedure taken up in Restoration works: Laying of GSB WBM Gr II
- iv Restored Length: WBM Gr III on Washout Portion

— 575m

B. For Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
- i Material being used in Restoration :
- ii Equipment/Tools being used in Restoration works:
- iii Procedure taken up in Restoration works :
- iv Restored Length :

Signature of JE/AF/EE

Signature

(Name of Inspector)

5/12/20
J.E

High
05.12.20
A.E.

05/12/20
E.E

प्रमंडल का नाम: ग्रामीण कार्य विभाग, कार्य प्रमंडल सोनपुर

कार्य का नाम:- सारण जिला अन्तर्गत दरियापुर प्रखंड में पोझी PWD रोड से से जितवारपुर भाया वली रामजीतपुर पथ का बाढ़ से क्षतिग्रस्त (FDR) पथांश का पूर्ण:स्थापन कार्य।

पथ की कुल लम्बाई:- 7.00कि०मी०

क्षतिग्रस्त पथ की लम्बाई:- 575मी०

प्राक्कलित राशि:-20.765 लाख

प्रतिवेदन


यह प्राक्कलन सारण जिला अन्तर्गत दरियापुर प्रखंड में पोझी PWD रोड से से जितवारपुर भाया वली रामजीतपुर पथ का बाढ़ से क्षतिग्रस्त (FDR) पथांश का पूर्ण:स्थापन कार्य का प्राक्कलन का तैयार किया गया है। इस वर्ष अत्यधिक वाढ़ आने के कारण Ch-3810M से Ch-3900m पथांश पानी में कई दिनों तक डूबे रहने के कारण पथ बिल्कुल क्षतिग्रस्त हो गया। पथ में CH- 5600मी० से CH-5630मी०, CH- 5700मी० से CH-5750मी०, CH-6100मी०-से CH-6200मी०, CH-6375m to 6425m एवं CH-6880मी० से CH 6950 मी० में बाढ़ के पानी का अधिक Current रहने के कारण पथ में भारी कटाव हुआ है। साथ ही साथ पानी में भी पथ से भारी वाहनों के आवागमन होने के कारण पथ में कई स्थानों पर एक फीट से डेढ़ फीट गहरा कई pot holes बन गये हैं, जिसके कारण पथ से आवागमन दुष्कर हो गया है।

प्रस्तावित प्राक्कलन में पथ के कटे हुए पथांश में आवश्यकतानुसार, GSB WBM Gr2 WBM Gr3 का प्रावधान किया गया है।

यह प्राक्कलन वर्तमान अनुसूचित दर पर तैयार किया गया है, जिसकी स्वीकृति आपेक्षित है।



कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा दरियापुर


05.12.20

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल दरियापुर



कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, सोनपुर

Restoration work of road from Pojhi PWD road to Jitwarpur via Ramjitpur


Length of road-	7.0km
ABSTRACT OF COST	
1. Cost of Emergent repair of road & Bridge	Rs. 1,837,831.10
2. Add 1% Labour Cess	Rs. 18,378.31
3. Add 12% GST	Rs. 220,515.73
Total	Rs. 2,076,523.14
Say	Rs. 2,076,500.00


Junior Engineer
RWD(W) Daryapur


05.12.20
Assistant Engineer
RWD(W) sub division Daryapur


Executive Engineer
RWD(W) DIV
Sonpur

T/A Approved for Rs. 20,765 (Twenty lakh Six thousand five hundred)


S.E. Chapra