



## GOVERNMENT OF BIHAR

NAME OF WORK- Restoration work of road from Sitalpur- Parsa road to Saraishaho

(FDR PART-A)

Length-5.49km

BLOCK-DARIYAPUR

### DETAILED PROJECT REPORT UNDER FDR(2245)

ESTIMATED COST

*Rs-4.036lac*

..PREPARED BY :-  
EXECUTIVE ENGINEER  
RWD(W) DIVISION  
SONPUR

Inspection Report for flood damage work

Date:

1. Name of PIUs- R. W D (W) DV Sonpur

2. Name of Block/Road- Daryapur, Parasa-Sitalpur road to Saraisaha

**A. For Road**

1. Damage Location/Chainage : CH-400m-4300m, CH-4500m-4600m

2. Damage Length : 400m

3. Nature of Damage : Road washed with road embankment

4. Details of Restoration :

i Material being used in Restoration

: No

ii Equipment/Tools being used in Restoration works:

- No

iii Procedure taken up in Restoration works

: filling blocks bats in portion. ELW in filling excavated should

iv Restored Length 400m

**B. For Bridge**

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AE/EE

Signature

(Name of Inspector)

10/12/20  
S.E.

10/12/20  
AE

13/12/20  
E.E.



प्रमंडल का नाम:

ग्रामीण कार्य विभाग, कार्य प्रमंडल सोनपुर

कार्य का नाम:-

सारण जिला अन्तर्गत दरियापुर प्रखंड में शीतलपुर-परसां रोड से सरैयासाहो पथ का बाढ़ से क्षतिग्रस्त (FDR) पथांश का पूर्णस्थापन कार्य।

पथ की कुल लम्बाई:- 5.49कि०मी०

क्षतिग्रस्त पथ की लम्बाई:- 40.00मी०

प्राक्कलित राशि:-4.036 लाख

## प्रतिवेदन


यह प्राक्कलन सारण जिला अन्तर्गत दरियापुर प्रखंड में शीतलपुर-परसां रोड से सरैयासाहो पथ का बाढ़ से क्षतिग्रस्त (FDR) पथांश का पूर्णस्थापन कार्य का प्राक्कलन का तैयार किया गया। पथ में CH- 800मी० से CH-811मी० में बाढ़ के पानी का अधिक **Current** रहने के कारण पथ में भारी कटाव हुआ है, जिसके कारण पथ से आवागमन अवरुद्ध हो गया है।

प्रस्तावित प्राक्कलन में पथ के कटे हुए पथांश में **Brick Bats** से भरकर एवं पथ के दोनों ओर मिट्टी भरकर क्षतिग्रस्त पथांश को पुर्नस्थापित किया गया है।

यह प्राक्कलन वर्तमान अनुसूचित दर पर तैयार किया गया है, जिसकी स्वीकृति आपेक्षित है।

  
10.12.20

नीय अभियंता  
ण कार्य विभाग  
प्रशाखा दरियापुर

  
10.12.20


सहायक अभियंता  
ग्रामीण कार्य विभाग  
कार्य अवर प्रमंडल दरियापुर


  
10.12.20


कार्यपालक अभियंता  
ग्रामीण कार्य विभाग  
कार्य प्रमंडल, सोनपुर

Restoration work of road from Sitalpur- Parsa road to Saraishaho


h of road-	5.49km
ABSTRACT OF COST	
ost of Emergent repair of road & Bridge	Rs. 357,219.96
d 1% Labour Cess	Rs. 3,572.20
d 12% GST	Rs. 42,866.40
Total	Rs. 403,658.56
Say	Rs. 403,600.00

  
Junior Engineer  
RWD(W) Dariyapur

  
10.12.20  
Assistant Engineer  
RWD(W) sub division Dariyapur

  
13.12.20  
Executive Engineer  
RWD(W) DiV  
Sonpur

T/A Approved for RS- 4,03,619.96 (Rupees Four Lacs Three Thousand Six Hundred) only.

  
21.1.21  
S.E. Chafon



**Restoration work of road from Sitalpur- Parsa road to Saraishaho**

Item of work	Nos	Length	width	Height	Quantity	unit	Rate	Amount
Providing and laying Brick Bats								
Placing tractor at loading point, loading with front end loader impong, turning for return trip excluding time for haulage and return trip.								
CH-400M to CH-418M	1	9.25	$\frac{(13.5+4.5)}{2}$	$\frac{(1.5+3.0+1.95)}{3}$	178.98			
					178.98	cum	1818.03	325391.51
Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5								
CH-400M to CH-418M	2	30	1.125	$\frac{(3.0+0.6)}{2}$	121.50			
CH-450M to CH-750M	2	10	1.125	$\frac{(0.6+1.10)}{2}$	19.25			
					140.75	cum	226.13	31828.46

**Rs. 357,219.96**

*[Signature]*  
18/12/20  
Junior Engineer  
RWD(W) Dariyapur

*[Signature]*  
10.12.20  
Assistant Engineer  
RWD(W) sub division  
Dariyapur

*[Signature]*  
12/12/20  
Executive Engineer  
RWD(W) DiV Sonpur