

GOVERNMENT OF BIHAR

NAME OF WORK:- Restoration work of road from PMGSY road to Giri tola village road

(FDR PART-A)

Length-1.50m

BLOCK-DARIYAPUR

DETAILED PROJECT REPORT

UNDER FDR(2.245)

ESTIMATED COST

Rs-2.436 Lacs

..PREPARED BY :-
EXECUTIVE ENGINEER
RWD(W) DIVISION
SONPUR

Inspection Report for flood damage work

Date:

1. Name of PIUs- R.W.D (10) DIV Sonber

2. Name of Block/Road- Daryapur, PMGSY road to Gir:tol village
road-

A. For Road

1. Damage Location/Chainage CH. 400m - CH. 450m

2. Damage Length : 50m

3. Nature of Damage : Road washout with GSI, WB, GRI, GRII

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works: yes

iii Procedure taken up in Restoration works

iv Restored Length

50m

Bricks bats.

filling of bricks bats in
ditch portion -

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :


i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:


iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AF/EE


Signature

(Name of Inspector)


ST/220
J.E
05.12.20
AE


ST/220
J.E

प्रमंडल का नाम: ग्रामीण कार्य विभाग, कार्य प्रमंडल सोनपुर

कार्य का नाम:- सारण जिला अन्तर्गत दरियापुर प्रखंड में PMGSY पथ से गिरि टोला ग्रामीण पथ का बाढ़ से क्षतिग्रस्त (FDR) पथांश का पूर्ण:स्थापन कार्य।

पथ की कुल लम्बाई:- 1.5कि०मी०

क्षतिग्रस्त पथ की लम्बाई:- 35मी०


प्राक्कलित राशि:-2.436 लाख


प्रतिवेदन


यह प्राक्कलन सारण जिला अन्तर्गत दरियापुर प्रखंड में PMGSY पथ से गिरि टोला पथ का बाढ़ से क्षतिग्रस्त (FDR) पथांश का पूर्ण:स्थापन कार्य का प्राक्कलन का तैयार किया गया है। इस वर्ष अत्यधिक बाढ़ आने के कारण Ch-400M से Ch-450m पथांश पानी में कई दिनों तक डूबे रहने के कारण पथ बिल्कुल क्षतिग्रस्त हो गया। पथ में CH- 4000मी० से CH-435मी० में बाढ़ के पानी का अधिक Current रहने के कारण पथ में भारी कटाव हुआ है। साथ ही साथ पानी में भी पथ से भारी वाहनों के आवागमन होने के कारण पथ में कई स्थानों पर एक फीट से डेढ़ फीट गहरा कई pot holes बन गये हैं, जिसके कारण पथ से आवागमन दुष्कर हो गया है।

प्रस्तावित प्राक्कलन में पथ के कटे हुए पथांश में Brick Bats से भरकर आवागमन चालू करने का प्रावधान किया गया है।

यह प्राक्कलन वर्तमान अनुसूचित दर पर तैयार किया गया है, जिसकी स्वीकृति आपेक्षित है।



कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा दरियापुर



05.12.20
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल दरियापुर


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, सोनपुर

Restoration work of road from PMGSY road to Giri tola village road


Length of road-	1.5km
ABSTRACT OF COST	
1 Cpost of Emergent repair of road & Bridge	Rs. 215,562.16
2 Add 1% Labour Cess	Rs. 2,155.62
3 Add 12% GST	Rs. 25,867.46
Total	Rs. 243,585.24
Say	Rs. 243,600.00


Junior Engineer
RWD(W) Dariyapur


Assistant Engineer
RWD(W) sub division Dariyapur


Executive Engineer
RWD(W) DIV
Sonpur


T/A Approved for Rs. 2436 Lakh (Rupees two lac forty three thousand Six hundred) only.



S.E. Chandra

Restoration work of road from PMGSY road to Giri tola village road

SI No	Item of work	Nos	Length	width	Height	Quantity	unit	Rate	Amount
		2	15.00			30.00	M	246.59	7397.78
4	Providing and laying Brick Bats								
	Placing tractor at loading point, loading with front end loader umpong, turning for return trip excluding time for haulage and return trip.								
	CH-400m to CH- 435m	1	35.00	$\frac{(9.2+6.5)}{2}$	0.90	105.98			
						105.98	cum	1818.03	192666.02
5	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5								
	CH-400m to CH- 450m	2	50.00	1.13	0.90	101.25			
						101.25	cum	226.13	22896.14
									215562.16


Junior Engineer
RWD(W) Dariyapur


05.12.20
Assistant Engineer
RWD(W) sub division
Dariyapur


Executive Engineer
RWD(W) DiV Sonpur