



GOVERNMENT OF BIHAR

NAME OF WORK:- Restoration work of road from Jitwarpur PMGSY path to
Jitwarpur Harijan tola Gramin path

(FDR PART-A)

Length-3.70m

BLOCK-DARIYAPUR

DETAILED PROJECT REPORT

UNDER FDR(2245)

ESTIMATED COST

Rs-5.773 Lacs

PREPARED BY :-
EXECUTIVE ENGINEER
RWD(W) DIVISION
SONPUR

Inspection Report for flood damage work

Date:

1. Name of PUU- R.W.D(W) DIV Sonpur

2. Name of Block/Road- Damyapur, Jitwarpur PMGSY road to Jitwarpur
Harigan talu Gramin Path

A. For Road

1. Damage Location/Chainage: CH-3350m-3365, CH-3450m-3468m

2. Damage Length

33m

3. Nature of Damage

4. Details of Restoration

Road Washout

i Material being used in Restoration

: No Brick, Sand & Earth

ii Equipment/Tools being used in Restoration works:

: Filling the ditch with brick

iii Procedure taken up in Restoration works

: Bats and EIW

iv Restored Length

33m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AE/EE

Signature

(Name of Inspector)

प्रमंडल का नाम: ग्रामीण कार्य विभाग, कार्य प्रमंडल सोनपुर

कार्य का नाम:- सारण जिला अन्तर्गत दरियापुर प्रखंड में जितवारपुर PMGSY पथ से जितवारपुर हरिजनटोला ग्रामीण पथ का बाढ़ से क्षतिग्रस्त (FDR) पथांश का पूर्ण-स्थापन कार्य।

पथ की कुल लम्बाई:- 3.70कि०मी०

क्षतिग्रस्त पथ की लम्बाई:- 33.30मी०


प्राक्कलित राशि:-5.773लाख


प्रतिवेदन


यह प्राक्कलन सारण जिला अन्तर्गत दरियापुर प्रखंड में जितवारपुर PMGSY पथ से जितवारपुर हरिजनटोला ग्रामीण पथ का बाढ़ से क्षतिग्रस्त (FDR) पथांश का पूर्ण-स्थापन कार्य का प्राक्कलन का तैयार किया गया। पथ में CH- 3350मी० से CH- 3365मी० एवं Ch.3450 मी० से Ch- 3468.3 मी० में बाढ़ के पानी का अधिक Current रहने के कारण पथ में भारी कटाव हुआ है, जिसके कारण पथ से आवागमन अवरुद्ध हो गया है।

प्रस्तावित प्राक्कलन में पथ के कटे हुए पथांश में Brick Bats से भरकर एवं पथ के दोनों ओर मिट्टी भरकर क्षतिग्रस्त पथांश को पुनर्स्थापित किया गया है।

यह प्राक्कलन वर्तमान अनुसूचित दर पर तैयार किया गया है, जिसकी स्वीकृति आपेक्षित है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा दरियापुर


10.12.20
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल दरियापुर


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, सोनपुर

Restoration work of road from Jitwarpur PMGSY path to Jitwarpur Harijan tola
Gramin path


Length of road-	
ABSTRACT OF COST	
1 Cpost of Emergent repair of road & Bridge	Rs. 510,846.12
2 Add 1% Labour Cess	Rs. 5,108.46
3 Add 12% GST	Rs. 61,301.53
	Total Rs. 577,256.12
	Say Rs. 577,300.00


Junior Engineer
RWD(W) Dariyapur


10.12.20
Assistant Engineer
RWD(W) sub division Dariyapur


Executive Engineer
RWD(W) DiV
Sonpur

T/A Approved for Rs- 5.773 lakh (Rupees Five lac Seventy Seven thousand
Three hundred) only.


S.E. Chakrabarti

Restoration work of road from Jitwarpur PMGSY path to Jitwarpur Harijan tola Gramin path

SI No	Item of work	Nos	Length	width	Height	Quantity	unit	Rate	Amount
		2	15.00			30.00	M	246.59	7397.78
4	Providing and laying Brick Bats								
	Placing tractor at loading point, loading with front end loader umpong, turning for return trip excluding time for haulage and return trip.								
	CH-3350m to CH- 3365m	1	15.00	$\frac{(9.2+6.5)}{2}$	0.90	105.98			
	CH-3450m to CH- 3468.3m	1	18.30	$\frac{(9.2+6.25)}{2}$	$\frac{(1.5+0.9)}{2}$	169.64			
						275.62	cum	1818.03	501077.10
5	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5								
	CH-3350m to CH- 3365m	2	20.00	0.60	0.90	21.60			
	CH-3450m to CH- 3468.3m	1	24.00	0.60	1.50	21.60			
						43.20	cum	226.13	9769.02
									510846.12


Junior Engineer
RWD(W) Dariyapur


10.12.20
Assistant Engineer
RWD(W) sub division
Dariyapur


Executive Engineer
RWD(W) DiV Sonpur