

(67)

(39)

Inspection Report For Flood Damage Work

Date:

1 Name of PIUs: Sopalganj - 2

2 Name of Block/Road: Bai Khatapur / 1029 - To 6 Khatiya Bighwa Dubai

A For Road

1 Damage Location / Chainage: 500 m to 1045 m, 1500 m to 1700 m, 2050 m to 2200 m

2 Damage Length: 309 m

3 Nature of Damage: Heavy Rain / Flood

4 Details of Restoration Works:

i. Material being used in Restoration Works: Brick Bats

ii Equipments / Tools being used in Restoration Works: JCB, Tractor, Trolly, Belcha, - shaver

iii Procedure taken up in Restoration Works: Yes

iv Restored Length: 309 m

B For Bridge

N/A

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

4 Details of Restoration Works:

i. Material being used in Restoration Works:

ii Equipments / Tools being used in Restoration Works:

iii Procedure taken up in Restoration Works:

iv Restored Length:

Signature
JE
25/4/2020

Signature
AE

Signature
EE
25/4/20

Signature
Executive Engineer
(Name)
R.W.D. W.D.
Hathua



ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR
DISTRICT :- GOPALGANJ
BLOCK :- BAIKUNTHPUR

L029-T06 Mathiya to Dighwa Dubauli

ESTIMATED COST - RS.

~~2002700.00~~
1696700.00

SUBMITTED BY :-
EXECUTIVE ENGINEER
RWD (W) DIVISION
GOPALGANJ-2

Report

Name of Work :- Motorable work of L029-T06 Mathiya to Dighwa Dubauli

Estimated Cost :- 2002700.00 Rs 1696700.00


Total length of Road :- 3.000 km

Description :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road. Hence there has been a provision of laying 2 Nos of R.C.C. NP3 1000 MM Dia hume pipe.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.


19/9/20
J.E.


18.09.2020
A.E.


19/9/20
E.E.

Detailed Estimate For Motorable Work in Road from L029-T06 Mathiya to Dighwa Dubauli damaged due to Heavy rain/flood for year 2020-2021

Sr.	Items	No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amount
1	Providing brick bats billed in ditches including all cost of labour & material with all complete job.								
	CH - 500 M to 1045 M	1	30.00	2.50	0.50	37.50	M3		
		1	15.00	2.50	0.60	22.50	M3		
		1	5.00	1.20	0.60	3.60	M3		
		4	30.00	4.00	1.30	624.00	M3		
		1	28.00	3.50	0.50	49.00	M3		
		1	16.00	2.00	0.40	12.80	M3		
	CH - 1500 M to 1700 M	1	7.00	2.00	1.00	14.00	M3		
		1	12.00	3.00	0.30	10.80	M3		
		1	5.00	2.00	0.55	5.50	M3		
		1	23.00	1.40	0.60	19.32	M3		
	CH - 2000 M to 2200 M	1	4.00	0.60	0.35	0.84	M3		
		1	8.00	1.20	0.30	2.88	M3		
		1	12.00	0.40	0.25	1.20	M3		
		1	20.00	1.20	0.30	7.20	M3		
		1	4.00	0.50	0.25	0.50	M3		
	Less for H.P.	1.58	1.23	1.23	5.00	11.95	M3	2412.11	1627909.20
						799.69		2427.65	1941362.79
2	Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	4	2.50			10.00	M	4159.56	1638392.07
								1655354	1982958.39
								1655420	19829.58
	Add 1 % Contingency							Total	2002787.98
								Say	2002700.00

[Signature]
19/9/2020
J.E.

[Signature]
13.03.2020
A.E.

[Signature]
15 1696700.00
1671908.20
16.7196
19/9/20
E.E.

For the purpose of work in front from 0.5-100 feet to 100 feet
 (Gibson) estimated the amount of work to be done for the year 2000

Technically Approved for Rs 16,719 lac (Peoples Street Line)
 Seventy one Thousand & Nine Hundred only

[Signature]
 Superintending Engineer
 R.W.D. Work Circle-Siwan
[Signature]
 24/11/2000