

FDR - BAIKUNTHPOR
2020

Schedule XLV-Form No. 134

DIVISION

Block - Baikunth Por

SUB-DIVISION

M.B.HO-538

MEASUREMENT BOOK

निर्माण किया जाता है कि इस
भाषा पुस्तक पंजी में अभिलेखित
है कि कुल 100 (एक सौ) पन्ने हैं
जिसे श्री चन्देश्वर सिंह के
नाम से निर्गत किया जाता है

16/9/20
कार्यपालक अभियंता
सर्वोच्च कार्य विभाग कार्य प्रमुख
गोपालगंज-2
16/09/2020

Sch. XLV - Form No. 134

DIVISION

SUB-DIVISION

Measurement Book

M.B. No. 538

Name of officer श्री चन्देश्वर सिंह

सहायक अभियंता लखनपुर

Date of first entry

Date of last entry

Sch. XLV-Form No. 134

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
Name of Work - Motorable work in Road from					
Kharica Aghara Mahalla Talu To Gaxauli					
P.M.G.S.Y Road, damaged due to Heavy					
rain/flood for Year 2020-2021					
Authority - Executive Engineer, R.W.D,					
Works Division, Gopalganj-2					
Agency - Departmental work.					
Measurement					
Item 1 Paving brick bats laid					
in situ, including all cost of labour					
and material, all comp. job.					
ch 100m to	1	26.00	5.00	0.30 m	39.00 m ³
260 m	1	30.00	4.50	0.50 m	67.50 m ³
	1	30.00	3.00	0.65 m	58.50 m ³
	1	15.00	4.00	0.60 m	36.00 m ³
	1	8.00	5.00	0.55 m	22.00 m ³
	1	19.14	6.00	0.84 m	96.47 m ³
	1	23.00	3.00	1.00 m	69.00 m ³
ch 400m to	1	8.00	5.00	0.60 m	24.00 m ³
530 m	1	16.00	6.00	1.50 m	144.00 m ³
	1	5.00	5.50	0.60 m	16.50 m ³
	1	20.00	4.00	1.40 m	112.00 m ³
	1	27.00	3.00	0.60 m	48.60 m ³
	1	30.00	2.50	0.20 m	15.00 m ³
Continuation					

Sch. XLV-Form No. 134

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
		8.7	-	-	= 748.57 m ³
	1	24.10	3.10	0.20	= 14.40 m ³
	1	17.10	4.10	0.20	= 13.94 m ³
	1	13.10	2.60	0.25	= 11.83 m ³
	1	20.10	1.65	0.50	= 16.50 m ³
	1	15.10	0.80	0.40	= 4.80 m ³
	0.79	1.23	1.23	5.00	= 5.98 m ³
				Total =	804.26 m ³

Item 2. Providing and laying 100mm dia
NP3 Hume Pipe in single row - job
2x 2.50 m - - = 5.00 m

(Signature)
18/01/21

ABSTRACT OF COST			
Item 1	Providing brick bats belled in ditch - - complete job		
804.06 m ³	@ Rs 2412.11/m ³	-	Rs 1939481.00
Item 2	Providing and laying 100mm dia NP3 Hume Pipe - - job		
5.00 m	@ Rs 2723.55/m	-	Rs 13668.00
	Total		Rs 1953149.00
	<i>(Signature)</i> 18/01/21		<i>(Signature)</i> 18/01/21

Continuation