Name of Work:-

Estimate for Repair of Road breaches (Damaged by Flood) for Motoribility in Ramgarhwa - Sukhisemra For year 2020.

1.				1		1 1	1	1	
tem No.	Name of Item	unit	S N	Length	Width	Height	Qty.	Rate	Amount
1	Earth work in Excavation for roadwork in soil with	cum	As Pe	r .	Ap	pendix	1477.500	382:47	609423.11
	hydraulic excavator of 0.9 cum bucket capacity including cutting Only and as per Technical Specification Clause							3827	5,65,0
	302.3	cum					157.50	2116.22	333304.65
1	Providing & Laying dry graded Brick Bats including light ramming etc. all complete as per approved design, specification and direction of E/I.	Cum	As Pe	er II		pendix			
2	Providing sand bag in side slope of shoulder and both side	Nos	As Pe	er	Ar	pendix	19412.00	27.83	540235.96
	of breached place of road including stitching, stacking and placing eith cost of sand including all taxes and carriage of materialdo do All complete			II	I				
	job as per specification and direction of E/I							40.00	19519.36
3	Rate for cutting 62 mm to 75 mm dia bamboo piles to size and making shoes and driving etc. complete job as per	М	100	4.5			450.00	43.38	
	specification and direction of E/I Rate for fitting and fixing 62 mm to 75 mm dia	М	100	2	\vdash		200	18.48	3695.31
4	bamboo runners in position at every vertical pile with 150mm long nails or 38swg G.I. wire including cost of G.I wire or nails complete job as per specification	1							
	and direction of E/I	M2	2 100	2	1.	5	300.00	152.81	45841.64
5	Rate for fitting and fixing split bamboo weven chachri in position with 20swg G.I. wire 75mm to 100mm long nails alternatively including cost of G.I wire or nails complete		100						
	job as per specification and direction of E/I						T	OTAL (in Rs.	1552920.03

Junior Engineer,
Rural Works Department,
Works Section, Ramyshiva

Assistant Engineer,
Rural Works Department,
Works Sub Division,

Executive Engineer, Rural Works Department, Works Division, Raxaul

Post facto TAITS is accorded for Rs. 15,08,000.00

(crore fifteenlass Eight thousand

SE. (R.W.)
works Cir
29.12. Zo